CC	DE A	NALYSIS	}	
	APPLICAI	BLE CODES		
International Building Co International Mechanica International Plumbing C International Fire Code International Energy Conservation Code	Code 2006	National Electrical Co		Year 2005
A. Occupancy and Grou	ip	TING CENTRAL HEATING F		 No
		i i tioo, oo voi oa ivialij.	<u>ANT</u>	HEATING h
C. Type of Construction	(circle one): EX	smic Report. See WSU Reports STING CENTRAL HEATING MEATING MEA	G PLAN	T <u>Z</u>
separation distance (in hours): N/A	s for the Exterior Walls base EXIST. West: EXIST.	d on the	fire
·	_N/A No	nseparated Uses: N/A		
F: Sprinklers:	NO		N .1	/A
	TWO Building or (square feet):	_ Type of Sprinkler System Height: 32' BASEMENT - LOWER FLOOR - 5400 SO UPPER FLOOR - 1326 SQ	FIRST F	
J: Area Modifications: No. 10 A _a = A _t + $\left[\frac{A_t I_f}{100}\right]$		$I_f = 100 \left[\frac{F}{P} - 0.2 \right]$	25 $\frac{W}{30}$	-
c) Total Allowable A 1) One Story: 2) Two Story: 3) Three Story: d) Unlimited Area B	A _a (2) A _a (3)	No Code S	Section:	
K. Fire Resistance Rati	ng Requirements	for Building Elements (hours	s). N/A	
Element	Hours Assembly Listing	Element	Hours	Assembly Listing
Exterior Bearing Walls Interior Bearing Walls Exterior Non-Bearing Walls Structural Frame Partitions - Permanent Fire Barriers		Floors - Ceiling Floors Roofs - Ceiling Roofs Exterior Doors and Windows Shaft Enclosures Fire Walls Fire Partitions Smoke Partitions		
L. Design Occupant Loa	d: <u>FLUCTUATE</u>	S-BETWEEN ONE TO SIX		
Exit Width Required:	E	Exit Width Provided: 21 L.F. EXISTING LOWE EXISTING UPPE	R LEVE	L-3 EXITS
Two lower level and a) Water Closets - I b) Lavatories - Re c) Bath Tubs or Sho d) Drinking Fountai e) Urinals:1	one upper level a Required (m) quired (m) owers;2 ns:2 S	ng Facilities: 3 EXISTING and one breakroom. All are u (f) Provided (m _ (f) Provided (m) ervice Sinks: 2 Provided: 1	nisex fa	cilities. _ (f)
through \(\mathbf{\U}\) - ADA Guide	elines and specific	nent of Justice Federal Regis c reference to the Internation estrictive requirement shall g	nal Build	
Official for Complex But a) High Rise Required b) Atriums. c) Performance Based) Means or Egresse) Fire Assembly Long fy Exterior and Inter	uildings. Including rements. sed Criteria. s Analysis. ocator Sheet.	oute.	e Buildin	g

*WORKSHOP IS EQUIPPED WITH A CABINET MOUNTED STAINLESS STEEL SINK AND EMERGENCY EYE - WASH AND SHOWER.

WEBER STATE UNIVERSITY HEATING PLANT - BOILER REPLACEMENT

DFCM PROJECT NO. #07049810 OGDEN CITY, UTAH



State of Utah—Department of Administrative Services


DIVISION OF FACILITIES CONSTRUCTION AND MANAGEMENT

4110 State Office Building / Salt Lake City, Utah 84114 / 538-3018



DRAWING INDEX:

G001 - COVER SHEET SE001 - GENERAL STRUCTURAL NOTES SE002 - GENERAL STRUCTURAL NOTES SB101 - FOOTING AND FOUNDATION PLAN SB401 - ENLARGED MAT FOOTING PLAN & DETAILS SF101 - ROOF FRAMING PLAN SF501 - ROOF FRAMING DETAILS M001 -- MECHANICAL GENERAL NOTES & LEGEND ME101 - LOWER LEVEL BOILER ROOM MECHANICAL AND PIPING PLAN ME102 - UPPER LEVEL BOILER ROOM MECHANICAL AND PIPING PLAN ME201 - NEW BOILER ELEVATIONS ME202 - CATWALK LAYOUT ME401 - LARGE SCALE ECONOMIZER ARRANGEMENT ME402 - LARGE SCALE PLANS AND ELEVATIONS BLOWDOWN SYSTEMS ME403 - LARGE SCALE FUEL OIL PLAN VIEW AND ELEVATIONS ME501 - MECHANICAL DETAILS ME601 - MECHANICAL SCHEDULES ME701 - FUEL OIL FLOW DIAGRAM ME702 - BOILER FEEDWATER FLOW DIAGRAM ME703 - PIPING AND INSTRUMENTATION DIAGRAM ME901 - PIPING ISOMETRICS ED101 -LOWER LEVEL BOILER ROOM DEMOLITION PLAN-ELECTRICAL EE001 -GENERAL NOTES, SCHEDULES AND DETAILS EE101 -LOWER LEVEL BOILER ROOM PLAN - ELECTRICAL





MECHANICAL ENGINEERS
WHW ENGINEERING, INC.
8619 SANDY PARKWAY
SUITE 101
SANDY, UTAH 84070
PHONE: (801) 466-8536



STRUCTURAL ENGINEERS
REAVELEY ENGINEERS
675 E. 500 SO.
SUITE 400
SALT LAKE CITY, UTAH 84102
PHONE: (801) 486-3883 FAX: (801) 485-0911

ELECTRICAL ENGINEERS

ECE ELECTRICAL CONSULTING
939 SO. WEST TEMPLE
SALT LAKE CITY, UTAH 84101
PHONE: (801) 521-8007 FAX: (801) 521-8057

I. Design Criteria

A. Governing Building Code: 2006 International Building Code (IBC)

B. Roof Live Loading: 1. Roof Live Load: 2. Roof Snow Load: . 30 psf + Drift per IBC a. Ground Snow Load, Pa: b. Snow Exposure Factor, C_e: . 1.0 Importance Factor, Is: . 1.0 . 1.0 d. Thermal Factor, Ct:

C. Earthquake: . Occupancy Category:

. Seismic Design Category.. 3. Spectral Response Accelerations: $S_s = ___ g$ $S_{DS} = 0.57 g$ $S_{D1} = _{_{_{_{_{_{_{0}}}}}}} g$ 4. Soil Site Class: .

5. Basic Seismic-Force-Resisting System: . Non-Structural component $R_p = 2.5$ $a_p = 1.0$ i. Importance Factor, Ip: .

Design Base Shear Bioler: 10 kips 8. Analysis Procedure: . Equivalent Lateral Force (Static)

D. Wind: (Existing Building)

E. Foundation: Subsurface Conditions:

Soils report and log of borings was obtained by the Owner for the Engineer's use in the design of the foundation, and is not a part of the Contract Documents. This report and log of borings is available for the Contractor's information, but is not a warranty of the subsurface conditions. The Contractor may use the report at his own risk.

2. Soils Report by No soils report – bearing pressures are light.

F. Classification for Fire Rated Construction:

1. For the purpose of determining fire-resistive assemblies, open-web steel framing members shall be considered unrestrained. All other steel floor and roof framing members shall be considered

2. Diagonal members in vertical braced frames shall be considered as secondary members for fire proofing protection

II. Earthwork

A. Clearing: The entire footing area shall be cleared of all existing structures, footings, and other debris. B. Remove all loose material from below footings and replace it with compacted structural fill. Provide a minimum of 12" of compacted structural fill below the footing.

C. Proof rolling: The natural undisturbed soil below all footings shall be proof rolled prior to placing concrete. Remove all soft spots and replace with compacted structural fill.

D. Compacted structural fill: All fill material shall be a well-graded granular material with a maximum size less than 4 inches and with not more than 10 percent passing a No. 200 sieve. It shall be compacted to 95 percent of the maximum laboratory density as determined by ASTM D1557. All fill shall be tested (See Specifications and the Quality Assurance section of the GSN).

III. Concrete

A. Materials shall comply with the Standards specified in American Concrete Institute (ACI) 318-05.

'Building Code Requirements for Structural Concrete.'' Compressive strengths of concrete at 28 days shall be as follows: a. Footings: b. Slabs on Grade: . 3000 psi

4000 psi c. All other Site Cast Concrete: Concrete Density (Maximum Air Dry Weight): a. Normal weight concrete shall be approximately 145 to 155 pounds per cubic foot.

b. Lightweight concrete shall not exceed 110 pounds per cubic foot and shall be made of lightweight coarse aggregates and a blend of lightweight and normal weight fines. Reinforcement steel:

a. ASTM A615 Grade 60, fy = 60,000 psi min. unless noted otherwise. b. Reinforcement at concrete moment frames and shear wall jambs shall be ASTM A706 or ASTM A615 Grade 60, with the following properties:

(1) Actual yield strength based on mill tests shall not exceed 78,000 psi. (2) Retest shall not exceed 81,000 psi.

(3) Ratio of actual ultimate tensile stress to the actual yield strength shall not be less than

(4) Mill tests shall be submitted to the Engineer. 4. Admixtures:

a. Air-entraining admixtures, comply with ASTM C 260 (when used).

(1) When air content of a trowel finished floor slab exceeds 3%, there is an increased risk for delaminations and blistering to occur. When this situation is present, the contractor shall pay special attention to the finishing procedures to help minimize such risks. Refer to ACI 302.1R-96 "Guide for Concrete Floor and Slab Construction" for proper finishing

b. Calcium chloride shall not be added to the concrete mix. 5. Only one grade or type of concrete shall be poured on the site at any given time. 6. Plastic coated tie wires and chairs shall be used to support reinforcing bars, tie bars and

B. Formwork shall comply with ACI Standards Publication 347 and the project specifications. The contractor shall be responsible for the design, detailing, care, placement and removal of the formwork and shores.

C. Concrete cover requirements for deformed bar reinforcing steel shall comply with ACI 318, "Building Code Requirements for Structural Concrete".

 Cast-in-place Concrete: Clear Cover a. Cast against and permanently exposed to earth: b. Formed concrete exposed to earth or weather: #6 thru #18 bars. 1.1/2" #5 and smaller bars. c. Concrete not exposed to weather or in contact with ground: Slabs, Walls, Joists; #11 bars and smaller. Beams, Columns: Primary Reinf., Ties, Stirrups, Spirals... .. 1.1/2" d. Concrete Tilt-Up Panels: #8 and smaller bars..

#9 thru #18 bars.. Pre-cast Concrete (manufactured under plant controlled conditions) a. Wall Panels #11 bars and smaller. Other members #6 thru #11 bars. . 1.1/2" Other members #5 bars and smaller.

Prestressed Concrete (Provide the following minimum cover for prestressed and non-prestressed reinforcements, ducts, and end fittings.):

 a. Cast against and permanently exposed to earth... b. Formed concrete exposed to earth or weather: Wall Panels, Slabs, Joists.. Other members Concrete not exposed to weather or in contact with ground:

Slabs, Walls, Joists..

Ties, Stirrups, Spirals.

Beams, Columns: Primary Reinf. .

D. Construction Joints and Control Joints:

1. Provide a continuous 2 X 4 keyway or a surface intentionally roughened to a full amplitude of approximately ¼" in all wall footings. Adjust the keyway as necessary to provide for proper bar placement. A continuous keyway shall not be used for concrete shear wall to footing connections, unless specifically indicated. Refer to project plans, schedules and details for the shear wall to footing connection requirements.

2. All horizontal and vertical construction joints shall have a continuous 2 X 4 keyway along the joint or joints shall be intentionally roughened to a full amplitude of approximately 14", unless noted

3. Provide reinforcement dowels to match the member reinforcement across the joint except for shear walls, unless noted otherwise. For dowels across construction joints and wall to footing connections of concrete shear walls, refer to specific project plans, schedules, and details.

4. Construction joints in suspended concrete pours shall be made at the center of spans. 5. Slabs on grade shall have construction or control joints spaced not to exceed 30 times the slab thickness in any direction. All discontinuous control or construction joints shall be reinforced with

2 - #4 x 48". See structural details. Construction joints shall not exceed a distance of 125'-0" o.c. in any direction. 6. Control joints shall be installed in slabs on grade so the length to width ratio of the slab is no more than 1.25:1. Control joints shall be completed within 12 hours of concrete placement.

Control joints may be installed by:

a. Saw cut a depth of 1/4 the thickness of the slab b. Tooled joints a depth of 1/4 the thickness of the slab

7. Control joints in visually exposed walls, unless noted otherwise: (Joints shall line up with masonry and architectural joints, see drawings.) a. Vertical control joints at 10'-0" on center.

b. Reinforcing shall be continuous through control and construction joints, unless noted c. Control joints in concrete foundation walls shall line up with masonry control joints.

8. Control joints shall be installed in suspended slabs over steel decking by sawcutting along all interior grid lines. Joints centered above the purlins shall be 3/4" deep and shall have #4 X 5'-0" at 16" o.c. reinforcing, placed perpendicular (and centered) to the purlin. Joints centered above the girders shall be 3/4" deep and shall have #4 X 10'-0" at 16" o.c. reinforcing placed perpendicular (and centered) to the girder. The #4 bar reinforcing centered above the grid lines is in addition to the specified WWF continuous throughout the suspended slabs over steel decking. Reinforcing shall be placed 1" below the top of the slab.

E. Detailing: All reinforcing, including WWF, shall be detailed, bolstered & supported to comply with ACI 315, "Details and Detailing of Concrete Reinforcement" and the Concrete Reinforcing Steel Institute (CRSI) recommendations. Reinforcing bars shall not be welded unless specifically shown on

1. Lap splice lengths shall be detailed to comply with the "Reinforcing Bar Lap Splice Schedule" contained within the contract drawings. Splices may be made with mechanical splices capable of 125% tension capacity of the bar being spliced. Mechanical splices shall be the positive connecting type coupler. They shall be covered by a current ICC Code Evaluation Report. Use "Cadweld" splice sleeves with ferrous filler, "Lenton" taper threaded rebar splices, "Bar-Lock" lockshear bolt coupling sleeves, or approved equivalent. If mechanical splices are used, splices or couplers on adjacent bars shall be staggered a minimum of 24" apart along the longitudinal axis of the reinforcing bars.

2. All embedments and dowels shall be securely tied to formwork or to adjacent reinforcing prior to

3. Use chairs or other support devices recommended by the CRSI to support and tie reinforcement bars and WWF prior to placing concrete. WWF shall be continuously supported at 36" o.c.

4. Contractor shall coordinate placement of all openings, curbs, dowels, sleeves, conduits, bolts, inserts and other embedded items prior to concrete placement.

5. All reinforcement shall be bent cold, and shall be bent only once at the same location. All reinforcement shall be shop bent, unless otherwise permitted by the engineer

IV. Structural Steel

A. Material:

1. W-Shapes: ASTM A992, (F_v = 50 ksi), except as noted otherwise. 2. All Other Shapes and Plates: ASTM A36 (Fy = 36 ksi), except as noted otherwise

3. Rectangular and Square Hollow Structural Sections (HSS): ASTM A500, Grade B (Fy = 46 ksi). 4. Round HSS: ASTM A500, Grade B (Fy = 42 ksi).

5. Steel Pipe: ASTM A53, Grade B (Fy = 35 ksi).

6. Deformed Bar Anchors (DBA): ASTM A496. . Headed Stud Anchors (HSA): ASTM A108, with dimensions complying with AISC specifications. 8. Anchor Rods: ASTM F1554, Grade 36 with ASTM A563 heavy hex nuts and ASTM F436

hardened washers, unless noted otherwise. 9. All steel shapes and plates which are a part of the seismic force resisting system shall have

Charpy V-Notch absorbed energy of 20 ft-lbs. or greater at 70 degrees Fahrenheit, as indicated

a. Shapes: Group 3 (with flanges 1.1/2" or thicker), Groups 4 and 5. b. Plates: 2" and thicker

c. Test Frequency: Each heat.

B. Fabrication and construction shall comply with the following Codes and Standards: 1. American Institute of Steel Construction (AISC) 360-05, "Specification for Structural Steel

Buildings." dated March 9, 2005. 2. AISC 341-05, "Seismic Provisions for Structural Steel Buildings" dated March 9, 2005, including

Supplement No. 1, dated November 16, 2005. 3. AISC 303-05, "Code of Standard Practice for Steel Buildings and Bridges" excluding the

following: Section 3.3 (last sentence of first paragraph), Section 4.4, Section 4.4.1, Section 4.4.2, Section 4.5, and Section 7.13.3. a. The architectural drawings are the prime contract drawings. Consultants' drawings by other

disciplines are supplementary to the architectural drawings. The structural drawings shall be used in conjunction with the architectural drawings. Detailing and shop drawing production for structural elements will require information (including dimensions) contained in architectural, structural, and/or other consultants' drawings. Refer to VII. Special Instructions, notes VII.B and VII.C on this sheet

4. AISC 358-05, "Prequalified Connections for Special and Intermediate Steel Moment Frames for Seismic Applications," dated December 13, 2005 AISC/RCSC 2004, "Specification for Structural Joints Using ASTM A325 or A490 Bolts"

6. American Welding Society (AWS) D1.1-04, "Structural Welding Code – Steel" (specific items do

not apply when they conflict with the AISC requirements) 7. Steel Joist Institute (SJI) 1994, "Standard Specification, Load Tables and Weight Tables for Steel

Joists and Joist Girders," and "Recommended Code of Standard Practice." 8. American Iron and Steel Institute (AISI) 2001, "North American Specification for the Design of Cold-Formed Steel Structural Members."

C. Structural shapes and plates shall be fabricated from newly rolled (milled) one-piece sections without splices, unless specifically noted otherwise on the structural drawings. Connections for structural steel shall comply with the structural drawings, unless written approval is given by the structural engineer.

1. Certification of Welders: All shop and field welding shall be executed by AWS certified welders who have been specifically certified for the type of work to be performed. Certification shall be considered current if dated within the past 12 months. Welders will be considered certified if they have been certified under AWS and their work records are current within every six-month period thereafter as required by AWS. Certification and records must comply with AWS Standards. Certification and appropriate records must be provided to the architect prior to beginning work.

2. Electrodes: E-70 XX or as noted otherwise. E60 XX may be used for welding steel floor and roof 3. Minimum Welds: All intersecting steel shapes that are not bolted shall be connected by a fillet weld all around, unless noted otherwise. Fillet weld sizes that are not shown shall be 1/16" less than the thinnest of the connected parts for thicknesses 1/4" and larger. Fillet welds on plates less than 1/4" shall be of the same size as the thinnest of the connected parts.

4. Reinforcing Bars: Do not weld rebar except as specifically detailed in the drawings. In such cases, use only AWS standards. Do not substitute reinforcing bars for deformed bar anchors (DBAs), machine bolts, or headed stud anchors (HSAs).

5. Bolts: Do not apply any welds, including "tack" welds to bolts, including anchor bolts, except as specifically detailed in the drawings.

6. It is recommended the steel erection contractor and steel fabricator contact the Quality Assurance Agency prior to beginning any of the above welds. A program of joint preparation and welding procedures should be worked out between the two parties before the welding is started so that correct welds will be made from the beginning.

7. Headed Stud Anchor (HSA) welding and Deformed Bar Anchor (DBA) welding shall conform to the manufacturer's specifications. Welding shall comply with AWS D1.1 Section 7.6 through 7.8 and Annex IX.

E. Bolted Connections: 1. Use ASTM A325N bolts for steel to steel connections, as noted herein or as noted on the drawings. A325N bolts shall be used in connections for simple span framing and beam (or girder) to bearing plate connections. Tighten bolts to a snug tight condition. A snug tight condition is usually attained by a few impacts of an impact wrench or the full effort of a man using

an ordinary spud wrench. Bolts shall be tightened until all plies of the joint are in firm contact. 2. Use ASTM A325N bolts for all steel to steel connections, unless noted otherwise. Tighten bolts by the turn of the nut, calibrated wrench, or direct tension indicator method. Alternate fastener designs as defined by AISC shall be submitted to the engineer for review and acceptability prior to installation. Provide hardened washers beneath turned element.

3. Use ASTM A325X bolts for all steel to steel connections, unless noted otherwise. Tighten bolts by the turn of the nut, calibrated wrench, or direct tension indicator method. Alternate fastener designs as defined by AISC shall be submitted to the engineer for review and acceptability prior to installation. Provide hardened washers beneath turned element.

4. Use ASTM A325SC bolts for all steel to steel connections in moment frames and connections subject to vibrations, unless noted otherwise. Tighten bolts by the turn of the nut, calibrated wrench, or direct tension indicator method. Alternate fastener designs as defined by AISC shall be submitted to the engineer for review and acceptability prior to installation.

5. Provide hardened washers beneath the turned element of all bolts or nuts. Provide hardened beveled washers, to compensate for the lack of parallelism, where the outer face of the bolted parts has a slope greater than one in twenty with respect to the plane normal to the bolt axis. Hardened washers or plates installed over oversized holes or slotted holes shall be at least 5/16" thick and shall conform to ASTM F436. Plates or bars installed at slotted holes shall have a size sufficient to completely cover the slot after installation.

6. Where a steel to steel beam connection is not detailed in the drawings, provide a standard AISC framed connection with the capacity to support one half of the total uniform load capacity of the given shape for the span and for the steel specified. 7. Bolts, nuts and washers shall not be reused.

F. Open Web Steel Joists and Girders:

1. The steel joist supplier shall be responsible for the design of all open web steel joists and girders. Joists or girders with slopes greater than 1/2 inch per foot shall be designed to meet or exceed the load capacities, listed in the SJI load tables, of the joist or girder sizes indicated on the

framing plan, as if the joists or girders were installed level. 2. Open web joists and girders shall be designed with deflection limits of L/240 for total load and L/360 for live load, where L is the joist span.

3. Where uplift loads due to wind are indicated, rows of bottom chord bridging shall be provided at the first bottom chord panel points per SJI Specifications. This is in addition to the bridging shown on the framing plans.

4. Provide special bearing ends to accommodate slopes from sloped joists, sloped girders or sloped bearing conditions.

5. Camber: All joists shall be cambered as specified in the SJI specifications, unless noted 6. Field Modifications: Do not modify any joist or girder, including holes through the top and bottom

chords, without the written consent and direction from the manufacturer. 7. Shop Drawings and Design Calculations: Shop drawings for all joists and girders used in the project shall be submitted for review. Prior to the fabrication of joists and girders, the open web steel joist and girder manufacturer shall prepare complete joist and girder calculations under the direct supervision of a professional engineer licensed in the State of Utah. Calculations shall be submitted for review for joists and girders designated as SPECIAL or SP and for all joists or girders with axial loads or additional concentrated loads (as noted on the drawings). Submitted

calculations shall bear the seal of a professional engineer licensed in the State of Utah. 8. Stabilizer Plates: Provide steel joist and joist girder stabilizer plates as indicated. Stabilizer plates shall be 6" x 6" with a 13/16" diameter hole with 1.1/2" minimum edge distance, and shall extend 3" minimum below the bottom chord of the joist or girder. Plate thickness shall be equal

to the chord gap minus 1/4", or 3/4", whichever is less. 9. Verify size, weight, location and configuration of all roof top equipment with architect and mechanical engineer. Provide steel frames for support of roof top equipment as indicated on structural details in the structural drawings. Coordinate openings with the mechanical and

10. All concentrated loads greater than 100 pounds supported by open web steel joists and girders shall be located within 6 inches of joist or girder panel points or the joist or girder shall be reinforced with an additional web member. Refer to the "TYPICAL DETAIL AT ADDITIONAL CONCENTRATED POINT LOAD" in the structural drawings.

11. Concentrated point loads, single or multiple, totaling 100 pounds or less can be located at any point along the top or bottom chord of an open web steel joist or girder between adjacent panel points without meeting the requirements above. A limit of four concentrated 100# maximum point loads per joist or girder will be permitted on spans of 12' or greater, one concentrated 100# max. load on spans less than 12', unless specifically noted otherwise on the structural drawings. Joist bridging shall never be used to support hanging loads.

13. Bracing of miscellaneous items (mechanical, electrical, plumbing, etc.) to the bottom chord of joists or girders will not be allowed in any instance. All lateral braces must connect to the top flange/top chord of the framing member above unless noted otherwise on the structural drawings.

G. Steel Roof Deck: 1. Steel roof deck shall comply with the latest requirements of the Steel Deck Institute (SDI). Submit ICC Code Evaluation Report with load and lateral shear capacities with shop drawings.

2. Steel roof deck shall be 1 1/2" deep X 20 Gauge minimum galvanized (G60), type "B" wide rib deck with interlocking side seams with the following properties:

<u> 20 Gauge</u> 0.234 Minimum S (in 3 /ft)=

0.213 Minimum I (in⁴/ft)= Painted roof deck shall be coated with special paint to receive sprayed-on fire proofing, where

Minimum allowable deck diaphragm shear values shall be 543 lb/ft. for a 6 ft. deck span. 4. Weld steel roof deck to supporting framing members with 3/4" diameter puddle welds at the following spacings (Closer spacings may be used to develop minimum shear requirements.): a. 6" o.c. to all supports perpendicular to deck corrugations (7 welds per 36" sheet).

b. 6" o.c. to the following supports parallel to deck corrugations: All perimeter supports, all concrete or masonry walls, all joists or joist girders with a "T/C" designation, and all steel beams which are on a grid line with braced frames or moment frames.

 c. 12" o.c. to all other supports parallel to deck corrugations. d. All welded surfaces shall be dry before welding deck to supports.

5. Attach interlocking seams with 1 1/2" long top seam welds at 12" o.c. minimum between adjacent pieces of decking. Crimp side seams before welding. Closer spacings may be used to develop minimum shear requirements.

6. Alternate means of deck attachment and fastening using screws, pins or other mechanical fastening methods are permitted with approval of the engineer. The contractor shall submit the proposed attachment system and the code evaluation report demonstrating the system has the strength to meet the required deck shears specified above (in item 3) and on the plans. The flexibility factor of the proposed deck attachment system shall be equal to or less than the flexibility factor for the specified welded deck attachment system. If the alternate attachment method is approved, it is the responsibility of the contractor to ensure that the deck type and profile is compatible with the fastening system being used.

7. Provide a 2" minimum bearing and a 4-inch lap at the splice points of all pieces of deck. 8. All deck shall be 3-span continuous minimum where possible. The contractor shall provide heavier gauge deck as required for one or two span conditions to meet equivalent loading of the above deck under a three span condition

Steel roof deck shall not be used to support loads from plumbing, HVAC ducts, light fixtures, architectural elements or equipment of any kind, unless specifically noted otherwise. Lightweight suspended acoustical ceilings with a total weight per wire not exceeding 50# may be hung from the steel roof deck. The hangers should be staggered to distribute the load over multiple deck SHEET NOTES State of Utah

> Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Department of Administrative Services

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



REAVELEY **ENGINEERS + ASSOCIATES** Consulting Structural Engineers

> 675 E. 500 S. Suite 400 Salt Lake City, UT 84102 P:801.486.3883 F:801.485.0911 www.reaveley.com

PROJECT NAME & ADDRESS

WEBER STATE UNIVERSITY HEATING PLANT - BOILER REPLACEMENT

DFCM No. 07049810

Ogden, Utah

MARK DATE REVISION

GENERAL STRUCTURAL NOTES

SE001

V. Special Instructions

- A. The project specifications are not superseded by the General Structural Notes but are intended to be complementary to them. Consult the specifications for additional requirements in each section. Notes and specific details on the drawings shall take precedence over General Structural Notes and
- B. The architectural drawings are the prime contract drawings. Consultant drawings by other disciplines are supplementary to the architectural drawings. All omissions or conflicts, including dimensions, between the various elements of the consultants' drawings and/or specifications shall be brought to the attention of the Architect before proceeding with any work involved. In case of conflict, follow the most stringent requirement as directed by the Architect without additional cost to the owner. Any work done by the contractor after discovery of such discrepancy shall be done at the contractor's risk.
- C. The structural drawings shall be used in conjunction with the architectural drawings. Primary structural elements and overall structural layout are indicated within the structural plans and details. Some secondary elements, architectural layouts, alcoves, elevations, slopes, depressions, curbs, mechanical equipment and electrical equipment, are not indicated within the structural drawings. Detailing and shop drawing production for structural elements will require information (including dimensions) contained in the architectural, structural and/or other consultants' drawings.
- D. Shoring and Bracing Requirements:
- 1. Floor and Roof Structures -- The General Contractor is responsible for the method and sequence of all structural erection. He shall provide temporary shoring and bracing as his method of erection requires to provide adequate vertical and lateral support. Shoring and bracing shall remain in place as the chosen method requires until all permanent members are in place and all final connections are completed, including all roof and floor attachments. The building shall not be considered stable until all connections are complete.
- 2. Foundation walls must be braced until the complete floor or roof systems is completed. Do not backfill until floor or roof systems are in place.
- 3. Walls above grade shall be braced until the structural system is complete. Walls shall not be considered to be self supporting.
- E. All expansion joints (E.J.) shown in the structural drawings shall be considered seismic separation joints, unless noted otherwise.
- F. Submittals: A copy of all shop drawings that have been submitted for review must be kept at the construction site for reference. These drawings must bear the appropriate review stamps. The shop drawing review shall not relieve the contractor of the responsibility of completing the project according to the contract documents. The general contractor shall review and mark all shop drawings prior to submitting them to the Architect for his review. Shop Drawings made from reproductions of (these) contract drawings will be rejected.
- G. Project Coordination: It shall be the responsibility of the general contractor to coordinate with all trades any and all items that are to be integrated into the structural system. Openings or penetrations through, or attachments to the structural system that are not indicated on these drawings shall be the responsibility of the general contractor and shall be coordinated with the Architect/Engineers. The order of construction is the responsibility of the general contractor. It is the contractor's obligation to provide all items necessary for his chosen procedure.
- H. Contractor shall field verify all dimensions, and conditions. If the contract drawings do not represent actual conditions, contractor shall notify architect/engineer prior to fabrication or construction within
- I. Notice of Copyright: The structural drawings, plans, schedules, notes and details are hereby copyrighted by Reaveley Engineers and Associates, Inc., All Rights reserved. Submission or distribution of documents to meet official regulatory requirements or for similar purposes in connection with the project is not to be construed as publication in derogation of Reaveley Engineers & Associates, Inc.'s reserved rights. The documents defining the structure are instruments of service prepared by Reaveley Engineers and Associates, Inc. for one use only. Furthermore, these documents shall not be reproduced, or copied, in whole or in part by the contractor or his subcontractors for preparation of shop drawings or other submittals.

VI. Quality Assurance

- A. Quality Assurance Agency Requirements:
- 1. The owner shall engage a qualified Quality Assurance Agency (QAA) to provide all special inspection and quality assurance testing for the project. All quality assurance personnel assigned to the project shall demonstrate competence, to the satisfaction of the building official,
- for inspection of the particular type of construction or operation requiring special inspection. 2. Prior to construction, the QAA shall prepare a written Quality Assurance Implementation Plan (QAIP) for the project. The QAIP shall include a list of personnel assigned to the project including management personnel, inspection procedures and frequency, proposed testing methods and frequency of testing, and reporting procedures. The QAIP shall also outline methods of documenting deficiencies and reporting corrections. A copy of the QAIP shall be given to the contractor for review and coordination with subcontractors.
- 3. Prior to construction, the QAA shall submit the following information to the Architect and Engineer of Record for approval:
- a. A copy of the Quality Assurance Implementation Plan for the project. b. A copy of the appropriate certification and training records for each individual performing
- c. A list of the testing equipment designated for the project and recent calibration records for
- the equipment. d. Sample inspection and testing reports and the distribution list for the reports.
- 4. The special inspector shall inspect the work per Chapter 17 of the IBC for conformance with the contract documents. The special inspector shall send reports to the owner, building official, architect, engineer, and contractor. All discrepancies shall be brought to the immediate attention of the contractor for correction. The QAA shall submit a final signed report stating that the special inspection work was, to the best of their knowledge, in conformance with the plans, specifications and applicable workmanship provisions of the IBC.
- B. Seismic Force Resisting Systems
- 1. Elements that are a part of the Main Seismic Force Resisting System for the structure may require increased quality assurance inspection and testing. The Main Seismic Force Resisting system for the structure includes the following elements:
- a. Roof decking. b. All elements labeled as "drag struts" or "chords."
- c. Connections between the elements referenced above.
- C. Special Inspection: Special Inspection shall be provided for the following elements per IBC sections
- 1. Concrete and elements embedded in concrete shall be special inspected prior to and during placement of concrete. Special inspection of concrete shall include the following:
- a. Reinforcing steel size and placement.
- b. Surface preparation at cold joints including placement of keyways.
- c. Bolt and embed size, configuration and placement.
- d. Concrete shall receive continuous special inspection during placement, and periodic inspection after placement to ensure proper curing and weather protection procedures.
- 2. Structural steel fabrication and erection shall be special inspected, including the following:
- a. High strength bolts per IBC 1704.3.3 and IBC section 2209. b. Fillet welds smaller than 5/16" per AWS D1.1
- c. Fillet welds larger than 5/16", multiple pass welds, and all groove welds shall receive continuous special inspection during weld placement per AWS D1.1.
- d. Welding of reinforcing steel shall receive continuous special inspection during weld
- placement per AWS D1.1.
- e. Welding of Headed Stud Anchors (HSA) and Deformed Bar Anchors (DBA) shall be inspected to comply with AWS D1.1 Section 7.6 through 7.8 and Annex IX.

f. Welding or fastening of floor or roof deck per AWS D1.3. or per the code evaluation report for

- the fastening method. g. Welding primary members of moment frames shall receive continuous special inspection to comply with AWS D1.1 and AISC 358, and the special provisions for moment frames in the structural steel sections of the GSN and specifications.
- 3. Post-installed anchors, including but not limited to expansion anchors, adhesive anchors and rebar dowels, and low velocity fasteners, shall receive special inspection per the code evaluation
- a. Continuous special inspection is required during the installation of all adhesive anchors and rebar dowels. Special inspector shall verify the following:
 - (1) Anchor size and steel grade. (2) Hole diameter, location, and type of drill bit.
 - (3) Cleanliness of hole and anchor.
 - (4) Adhesive application. (5) Anchor embedment.
- D. Structural Testing: The following materials shall be tested per IBC sections 1704 and 1708. The owner reserves the right to test any and all materials using any appropriate non-destructive procedure. Any items found to be deficient shall be corrected and retested at no additional cost to
- 1. Earthwork: All compacted structural fill shall be tested to verify soil gradation, lift thickness, and compaction requirements. See the specifications and earthwork section of the GSN for testing
- frequency and acceptability criteria. 2. Concrete Strength Verification and Testing. All concrete shall be tested to verify strength, slump, unit weight, air content, and temperature. See the specifications for testing criteria, testing
- frequency and acceptability criteria. 3. Welded connections shall be tested for compliance according to IBC Table 1704.3, AWS D1.1
- and the contract specifications and plans. As a minimum, the testing shall include the following: a. All complete penetration groove welds shall be tested 100 percent either by ultrasonic testing
- or by radiography. b. Partial penetration groove welds shall be tested either by ultrasonic testing or radiography. A minimum of 50% of these welds shall be tested.
- c. Base metal thicker than 1 1/2", when subjected to through thickness weld shrinkage strains, shall be ultrasonically inspected for discontinuities directly behind such welds and three inches above and below the weld after joint assembly completion.
- d. Any material discontinuities shall be accepted or rejected on the basis of the defect rating in accordance with the testing in AWS D1.1 Chapter 6, excluding Sections 6.1 through and including 6.6. All deficient welds shall be corrected and retested at no additional cost to the
- 4. Post-installed anchors, including but not limited to expansion anchors, adhesive anchors, and low velocity fasteners, shall be tested per the code evaluation reports for the anchors.
- E. Structural Observations by the Engineer of Record.
- The Engineer of Record may perform structural observations at critical phases of the project. Copies of the engineer's report will be distributed to the architect, contractor, owner, and QAA.
- 2. Observation visits to the site by the Engineer's field representatives shall not be construed as inspection or approval of construction.
- 3. Notification of Engineer: The contractor shall notify the engineer twenty-four hours prior to: a. Placing concrete in any footing.
- b. Closing any wall forms.
- c. Placing concrete in any column, beam or suspended slab. d. Grouting any masonry.
- e. Completing the welding of major sections of steel decking.
- f. Completing the nailing of any plywood wall or deck. F. Contractor Responsibility: The contractor shall prepare and submit a written statement of responsibility to the building official and the owner prior to commencement of work on the project. As
- a minimum the statement shall contain the following information: 1. Acknowledgement of the quality assurance requirements for the structure.
- 2. Acknowledgement of receipt of the Quality Assurance Implementation Plan (QAIP) from the testing agency.
- 3. Acknowledgement that control will be exercised to obtain conformance to the Contract Documents and the QAIP.
- 4. Quality control procedures within the contractors organization, methods and frequency of reporting, and distribution of the reports.
- 5. Identification and qualifications of the person(s) responsible for quality control and their position(s) in the organization.

ABBREVIATIONS ANCHOR BOLT (S) F.D FLOOR DRAIN NIC NOT IN CONTRACT ABOVE NTS NOT TO SCALE FOUNDATION FINISH FLOOR ALT ALTERNATE FINISH OPNG APPROX APPROXIMATE **FLOOR** OPP OPPOSITE ARCH ARCHITECT(URAL) FOOT ON CENTER OUTSIDE FACE FOOTING OWSJ OPEN WEB STEEL JOIST FIELD VERIFY BLW BELOW PCF GAUGE POUNDS/CUBIC FOOT BRG BEARING GALVANIZED BETWEEN POUNDS/LINEAL FOOT GLB GR GLU—LAMINATED BEAM BLDG BUILDING GRADE BOT BOTTOM PSF POUNDS/SQ FOOT GENERAL STRUCTURAL POUNDS/SQ INCH C.J. CONSTRUCTION JOINT POINT OR CONTROL JOINT HORIZONTAL BRIDGING REINF REINFORCING COMPLETE JOINT HEIGHT R.D. ROOF DRAIN PENETRATION HORIZ HORIZONTAL HSA HEADED STUD ANCHORS req'd required CMU CONC MASONRY UNIT COL COLUMN CONC CONCRETE INTERNATIONAL BUILDING CONST CONSTRUCTION SPECIAL INSPECTION ICBO INTERNATIONAL CONFERENCE SOG SLAB ON GRADE CONTINUOUS CONTR CONTRACTOR OF BUILDING OFFICIALS STD STANDARD STIFF CTR CENTER INTERNATIONAL CODE STIFFENER STL STEEL COUNCIL SQ SQUARE DECK BEARING INCH INSUL INSULATION SIMILAR DEFORMED BAR ANCHORS SIM INTERIOR STR STRUCTURAL STAG INSIDE FACE STAGGERED DETAIL TOP AND BOTTOM DIAMETER JOIST TEMP TEMPERATURE DIM DIMENSION THDS KIPS PER LINEAL FOOT DOWN THREADS DN KIPS PER SQUARE FOOT T.O. DWG DRAWING TOP OF TOC DWL KIPS PER SQUARE INCH TOP OF CONCRETE DOWEL KIPS - 1.000 POUNDS TOF TOP OF FOOTING TOP OF SLAB LINEAL FOOT TOW TOP OF WALL E.J. EXPANSION JOINT (SEISMIC SEPARATION JOINT) LBS POUNDS TYP TYPICAL ÉLEVATION LONG LEG HORIZONTAL ELEC UNO UNLESS NOTED OTHERWISE **ELECTRICAL** LLV LONG LEG VERTICAL EQUIP **EQUIPMENT** VERT VERTICAL EQ MASONRY EQUAL MAXIMUM WITH EXISTING WWF WELDED WIRE FABRIC MCJ MASONRY C.J. EXPANSION / EXPOSED MECH MECHANICAL EXTERIOR

PLAN MARKS BF-# BRACED FRAME CSS-# CONC SUSPENDED SLAB ML-# MASONRY LINTEL CSW-# CONC SHEAR WALL CONCRETE BEAM CONCRETE COLUMN MW-# MASONRY WALL CW-# CONCRETE WALL PD-# PLYWOOD DIAPHRAGM CONTINUOUS FOOTING CDP-# CONC DRILLED PIER PSW-# PLYWOOD SHEAR WALL MAT FOOTING CFW-# CONC FDTN. WALL RECTANGULAR FOOTING CGB-# CONC GRADE BEAM SQUARE FOOTING SBP-# STEEL BASE PLATE SC-# STEEL COLUMN CJ-# CONCRETE JOIST THICKEND SLAB FOOTING CONCRETE LINTEL SCP-# STEEL CAP PLATE SD-# STEEL DECK CONCRETE PIER CONC RETAINING WALL $\mathsf{MF} extstyle- extstyle\#$ MOMENT FRAME CSG-# CONC SLAB ON GRADE

MFR MANUFACTURER

MINIMUM

MISC MISCELLANEOUS

EACH FACE

EACH WAY

E.W.

SHEET NOTES

State of Utah Department of Administrative Services

> Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



REAVELEY **ENGINEERS + ASSOCIATES** Consulting Structural Engineers

> 675 E. 500 S. Suite 400 Salt Lake City, UT 84102 P:801.486.3883 F:801.485.0911 www.reaveley.com

PROJECT NAME & ADDRESS

WEBER STATE UNIVERSITY HEATING PLANT - BOILER REPLACEMENT

DFCM No. 07049810

Ogden, Utah


MARK DATE REVISION


WHW JOB NO.:


GENERAL STRUCTURAL NOTES


154201 ARTHUR PARRY

SE002









Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018

SALT LAKE CITY, UTAH 84106 (801)466-4021, FAX 466-8536 EMAIL: excellence@whw-engineering.com



UNIVERSITY HEATING **PLANT - BOILER**

			M	ECH	IANICAL LEGEND			
SYMBOL	ABR.	DESCRIPTION	SYMBOL	ABR.	DESCRIPTION	SYMBOL	ABR.	DESCRIPTION
		GENERAL TERMINOLOGY			WET SIDE			WET SIDE CONT
A		- SECTION LETTER DESIGNATION	<u> </u>		UNION			SLOPE
ME-101		-SECTION DRAWN ON THIS SHEET	Г		MANUAL ACTUATOR (BALL,	0		ELBOW UP
(A2)		- DETAIL NUMBER DESIGNATION			BUTTERFLY, NEEDLE, ETC. VALVES)	-		ELBOW DOWN
AZ		CORRESPONDING WITH GRID LOCATION	\top		MANUAL ACTUATOR (GATE, GLOBE,	$\overline{}$		TEE UP
AH		- MECHANICAL EQUIPMENT DESIGNATION			S&D, OS&Y, ETC. VALVES)			TEE DOWN
1		- EQUIPMENT ITEM DESIGNATION			THREADED OR SWEAT VALVE CONNECTION			EXISTING PIPING TO BE REMOVED
Â		REVISION DESIGNATOR AND NUMBER	₹		NEEDLE VALVE			EXISTING PIPING TO REMAIN
1		KEY NOTE DESIGNATOR AND NUMBER			FLANGED VALVE CONNECTION			NEW PIPING
•	POC	POINT OF CONNECTION	——————————————————————————————————————		BUTTERFLY VALVE			PIPE CAP OR PLUG
•	POR	POINT OF REMOVAL			GATE VALVE			CONCENTRIC REDUCER
AFF		ABOVE FINISHED FLOOR			CHECK VALVE			ECCENTRIC REDUCER
€ EL.		CENTER LINE ELEVATION		PRV	PRESSURE REDUCING VALVE			EXPANSION JOINT
GC		GENERAL CONTRACTOR	¥	CBV	CIRCUIT BALANCING VALVE	—-G-		NATURAL GAS PIPING
МС		MECHANICAL CONTRACTOR	—Ф—	BV	BALL VALVE		CW	CULINARY COLD WATER
EC		ELECTRICAL CONTRACTOR		PRV	PRESSURE RELIEF VALVE	— D —		EQUIPMENT DRAIN
СС		CONTROLS CONTRACTOR	<u></u>		AUTOMATIC AIR VENT	— CR —		CONDENSATE RETURN
NIC		NOT IN CONTRACT	-		MANUAL AIR VENT	—HPR —		HIGH PRESSURE RETURN
NTS		NOT TO SCALE			STRAINER	— PC —		PUMPED CONDENSATE
SYMBOL	ABR.	DESCRIPTION			STRAINER W/ PLUGGED BLOW OFF			GLOBE VALVE
		EXISTING EQUIPMENT TO BE REMOVED		VTI	VENTURI	−BFW −		BOILER FEEDWATER
		EXISTING EQUIPMENT TO REMAIN	Q		PRESSURE GAUGE AND GAUGE COCK -	-Fos -		FUEL OIL SUPPLY
		NEW EQUIPMENT			WATER	−FOR −		FUEL OIL RETURN
					THERMOMETER AND THERMOWELL	— AS —		ATOMIZATION STEAM
					THERMOMETER AND THERMOMELE	#	BPV	BACK PRESSURE VALVE
			———	TW	THERMOWELL			
			-		DIRECTION OF FLOW			
					PRESSURE GAUGE WITH SIPHON LOOP STEAM			

State of Utah Department of Administrative Services

Division of Facilities

Construction & Management ☐ 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



GENERAL NOTES:

COMPLIANCE.

DIMENSIONS.

EQUIPMENT AND CONTROLS.

ATTENTION PRIOR TO BIDDING.

CAPACITIES, OR DESIGN INTENT.

WORK OUTLINED BY THIS PROJECT.

AND REQUIREMENTS.

MECHANICAL INFORMATION IS NOT LIMITED TO THE MECHANICAL

A - EACH DRAWING SHEET AND THE SPECIFICATIONS HAVE BEEN

INTERPRETED AS AN INTEGRAL UNIT WITH ITEMS SHOWN AND NOTED

ON ONE AND NOT THE OTHER BEING FURNISHED AND INSTALLED AS

INSTALLATION OF THE SYSTEMS ACCORDING TO THE TRUE INTENT AND

C - THE CONTRACTOR SHALL INSTALL ALL EQUIPMENT WITH PROPER SERVICE ACCESS AND CLEARANCES ACCORDING TO MANUFACTURERS RECOMMENDATIONS. THE CONTRACTOR SHALL REVIEW SUPPLIERS BID

SPECIFICATIONS, SCHEDULES, AND DESIGN INTENT (ALL EQUIPMENT AND METHODS). THE CONTRACTOR SHALL REMOVE AND REINSTALL

INSTALLATION INSTRUCTIONS FOR SIZES, METHODS, ACCESSORIES, AND CLEARANCES IN SPACE AVAILABLE PRIOR TO BIDDING PROJECT.

E - ANYTHING NOT CLEAR OR IN CONFLICT WILL BE EXPLAINED BY

ANY AND ALL ALTERATIONS TO THE SYSTEM SHOWN SHALL BE

G-3 CONTRACTOR SHALL FIELD VERIFY ALL DIMENSIONS AND LOCATIONS.

INSTALLATION IN THE SPACE PROVIDED. ALL LOCATIONS FOR MECHANICAL EQUIPMENT SHALL BE FIELD VERIFIED AND

COORDINATED WITH ALL DRAWINGS. THE CONTRACTOR SHALL PROVIDE OR COORDINATE WITH THE GENERAL CONTRACTOR

THE INSTRUCTION TO "PROVIDE" ALSO INCLUDES INSTALLATION.

SHEET METAL DUCT SIZES SHOWN ON DRAWINGS ARE FREE AREA

THE MECHANICAL CONTRACTOR SHALL VERIFY MOTOR VOLTAGES WITH THE ELECTRICAL DRAWING BEFORE ORDERING MOTORIZED

SUPPLIERS SHALL REVIEW ALL DRAWINGS AND THE SPECIFICATIONS PRIOR TO SUBMITTING PRICES TO THE CONTRACTOR. ALL QUESTIONS

CONTRACTOR SHALL THOROUGHLY REVIEW AND SIGN SUBMITTALS

PRIOR TO ENGINEERS REVIEW. SUPPLIERS SHALL HIGHLIGHT OR MARK

FOR COMPLETENESS AND COMPLIANCE TO THE SPECIFICATIONS

SPECIFICATIONS, OR SCHEDULES SHALL BE CLEARLY NOTED AND

EXPLAINED. SUBMITTAL REVIEW AND ACCEPTANCE IS FOR DESIGN

ALL MECHANICAL AND PLUMBING SHALL BE INSTALLED AND CONFORM

TO THE 2006 EDITION OF THE IMC AND IPC WITH UTAH ANNOTATIONS

THIS CONTRACTOR SHALL BE RESPONSIBLE FOR THE DRAINING DOWN

AND RE-FILLING OF ALL SYSTEMS NECESSARY TO COMPLETE THE

ALL PIPING, MATERIALS, ETC. SHALL BE NEW AND DOMESTIC MADE

UNLESS SPECIFICALLY AUTHORIZED IN WRITING PRIOR TO BID.

ALL INFORMATION REQUIRED TO SHOW COMPLIANCE TO THE

SPECIFICATIONS. ALL REQUESTED EXCEPTIONS TO THE

CONCEPT ONLY, AND DOES NOT AT ANY TIME RELIEVE THE

CONTRACTOR OF RESPONSIBILITY TO MEET SPECIFICATIONS,

AND DISCREPANCIES SHALL BE BROUGHT TO THE ENGINEERS

SUBMITTED TO THE ENGINEER PRIOR TO CHANGES FOR APPROVAL. CONTRACTOR SHALL NOT START ANY CHANGES UNTIL NOTIFIED IN WRITING. IF CHANGES ARE MADE PRIOR TO APPROVAL CONTRACTOR SHALL TAKE ALL RESPONSIBILITY FOR THE CHANGES MADE AND ALL COSTS RELATING TO FAILURE OR REPLACEMENT OF ALTERATIONS.

THE WORKING DRAWINGS ARE DIAGRAMMATIC. THEY DO NOT SHOW EVERY OFFSET, BEND, OR ELBOW NECESSARY FOR THE COMPLETE

PROVISIONS FOR BLOCKOUTS OR CORE DRILLS THROUGH STRUCTURE.

SPECIFICATIONS OR DRAWINGS LISTED WHICH ARE DIFFERING IN

EFFICIENCY OR QUALITY SHALL BE HELD TO THE GREATEST OF:

PREPARED TO SUPPLEMENT EACH OTHER AND THEY SHALL BE

THOUGH SHOWN AND CALLED OUT IN ALL PLACES. ITEMS IN

B - THE CONTRACTOR WILL BE HELD RESPONSIBLE FOR THE

PACKAGES FOR COMPLETENESS AND COMPLIANCE TO THE

CORRECTLY AT HIS OWN EXPENSE ANY EQUIPMENT NOT IN

D - THE CONTRACTOR SHALL CONSULT MANUFACTURERS

MAKING APPLICATION TO THE ENGINEER IN WRITING.

OTHER DISCIPLINES AND SPECIFICATIONS.

EFFICIENCY, QUALITY OR GOVERNING CODE.

MEANING OF THE CONTRACT DOCUMENTS.

DRAWINGS. CONTRACTOR SHALL BE RESPONSIBLE FOR INFORMATION ON ALL OTHER CONSTRUCTION DOCUMENTS INCLUDING DRAWINGS BY

> **WHW ENGINEERING INC.** PROFESSIONAL MECHANICAL ENGINEERING 8619 Sandy Parkway Suite 101 SANDY, UTAH 84070 (801)466-4021, FAX 466-8536

PROJECT NAME & ADDRESS


WEBER STATE UNIVERSITY **HEATING PLANT -BOILER** REPLACEMENT

DFCM No. 07049810

Ogden, Utah


MARK	DATE		F	REVISION	
PROJEC	T MANAGE				
	CI W	'			

04/11/08 WHW JOB NO.: 07037 SHEET TITLE



MECHANICAL GENERAL NOTES AND LEGEND

M001



- SHEET NOTES: 1 NEW 30,000 #1HR BOILER, LOCATE AS SHOWN. FIELD VERIFY ROUTING OF BOILER PATH FROM ROOF TO PAD. SEE STRUCTURAL DRAWINGS FOR FOUNDATION DETAILS.
- 2 NEW BOILER CONCRETE PAD. SEE STRUCTURAL DRAWINGS FOR DETAILS.
- (3) CONNECT NEW 3" BOILER FEED WATER TO EXISTING 2-1/2" VALVE AT THIS LOCATION. FIELD VERIFY EXACT LOCATION. PROVIDE COMPANION FLANGE TO MEET PRESSURE OF EXISTING VALVE.
- 4 PROVIDE NEW BOILER FEEDWATER CONTROL STATION. SEE PIPING ISOMETRIC A3/ME901.
- (5) CONNECT NEW 3" GAS PIPING TO EXISTING GAS PIPING AT THIS LOCATION. FIELD VERIFY EXACT LOCATION.
- 6 SEE SHEET ME403 FOR LARGE SCALE PLAN AND ELEVATION OF THIS AREA.
- (7) CONNECT NEW 1-1/4" FUEL OIL RETURN PIPING TO EXISTING 1-1/4" VALVE ON RETURN HEADER THAT SERVED THE REMOVED BOILER #2. REMOVE CAP LEFT BY DEMOLITION CONTRACTOR. SEE SHEET
- (8) PROVIDE 1-1/4" BOILER BLOWDOWN PIPING COMPLETE WITH TANDEM VALVES, SUPPORTS, ETC. SEE DETAIL A2 AND C2 SHEET ME402.
- (9) INSTALL NEW FLEXIBLE STACK CONNECTION TO NEW BOILER PROVIDED BY BOILER MANUFACTURER.
- OTHERS. SEE DETAILS AND ARRANGEMENTS ON SHEET ME401. (11) EXISTING BOILER #3 ECONOMIZER SHALL
- (12) EXISTING CONDENSATE RECEIVER TANKS SHALL REMAIN.
- (13) EXISTING BOILER FEEDWATER PUMPS SHALL REMAIN. (14) EXISTING WATER SOFTENING SYSTEM SHALL
- REMAIN. (15) EXISTING NIPPER SHALL REMAIN. SEE LARGE SCALE PLAN AND ELEVATION A4 AND C4 ON SHEET ME402.
- (16) EXISTING DOOR TO GRADE
- $\langle \overline{17} \rangle$ EXISTING TREATMENT TANKS SHALL REMAIN. 1/2" TREATMENT LINE TO REMOVED BOILER #1 SHALL BE REMOVED AND CAPPED AT PUMP VALVE. SEE NOTES 46, 47, 48.
- (18) EXISTING BOILER FEEDWATER PIPING SHALL
- (19) EXISTING TRENCH DRAIN SYSTEM SHALL
- (20) EXISTING AIR COMPRESSOR SHALL REMAIN.
- (21) EXISTING GAS PIPING SHALL REMAIN.
- 22 EXISTING STAIRS FROM BOILER ROOM FLOOR TO EXIT AND CONTROL ROOM.
- 23 2-1/2" BOILER FEED WATER TO ECONOMIZER AND NEW BOILER. SEE PIPING ISOMETRIC A3/ME901.
- ②4〉 SEE BOILER FRONT PIPING ELEVATIONS AND DETAILS SHEET ME201.
- BOILER TO EXISTING STEAM HEADER CONNECTION.
- ⟨26⟩ SEE ME102 FOR RELIEF VALVES AND RELIEF PIPING THROUGH ROOF. SEE DETAIL
- D5/ME501. 27 27" DIA. BOILER STACK THROUGH ROOF. SEE DETAIL A3/ME501.
- (28) ROUTE GAS, FUEL OIL, BLOWDOWN, AND BOILER FEEDWATER PIPING A MINIMUM OF
- 9'-6" ABOVE FLOOR TO CENTER LINE OF 29 DROP GAS LINE DOWN AND CONNECT TO GAS TRAIN. SEE GAS TRAIN ISOMETRIC
- 30 FILL EXISTING TRENCH AND PROVIDE NEW BOILER FOUNDATION. SEE STRUCTURAL SB401 DRAWINGS FOR FILL AND NEW PAD FOUNDATION.
- (31) 2" DRAIN THROUGH FLOOR AND TROUGH SHALL REMAIN. REMOVE DRAIN PIPING IN TROUGH THAT IS NO LONGER USED. VERIFY WHAT WAS REMOVED BY DEMOLITION CONTRACTOR.
- (32) EXISTING PIPE SUPPORTS.

SHEET C3/ME901.

- (33) SEE SHEET ME102 FOR CONTINUATION.
- (34) EXISTING CONDENSATE TRANSFER PUMPS SHALL REMAIN.
- (35) EXISTING DEAERATOR AND CONDENSATE RECEIVER TANK, STRUCTURAL SUPPORTS SHALL REMAIN.
- (36) EXISTING FLOOR DRAINS IN INDENTED FLOOR SHALL REMAIN.
- 37 SEE PLAN AND ELEVATION SHEET ME402 FOR DETAIL OF CONTINUOUS BLOWDOWN PIPING THIS AREA.
- $\langle 38 \rangle$ EXISTING FLOOR INDENTATION.
- (39) NEW 10" DIA. F.G.R DUCT- PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY THIS CONTRACTOR.
- 40 EXISTING BOILER #3 SHALL REMAIN.
- 41 EXISTING BOILER #4 SHALL REMAIN.
- (42) NEW 1-1/2" FUEL OIL SUPPLY TO NEW BURNER SEE SHEET ME201 FOR ELEVATION AND SHEETS ME403 AND ME701 FOR DETAILS.
- (43) NEW 1-1/4" FUEL OIL RETURN PIPING. SEE SHEETS ME201 FOR ELEVATION AND SHEETS ME403 AND ME701 FOR DETAILS AND FLOW SHEETS.

State of Utah Department of Administrative Services

Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



PROJECT NAME & ADDRESS

WEBER STATE UNIVERSITY **HEATING PLANT -BOILER** REPLACEMENT **DFCM No. 07049810**

REVISION

Ogden, Utah

PROJECT	MANAGE	:D·			
1	\cap \cup \vee \wedge \wedge		/		

MARK DATE


SLW/WP 04/11/08 VHW JOB NO.: 07037

SHEET TITLE

LOWER LEVEL BOILER ROOM MECHANICAL AND PIPING PLAN

 $^{\circ}$ /WINWARD M $^{\circ}$

PACKER



UPPER LEVEL BOILER ROOM PLAN

SHEET NOTES:

- 1 NEW 30,000 #/HR STEAM BOILER B2.
- 2 NEW ECONOMIZER ECO-2 AND STACK
- THROUGH ROOF. SEE NOTE 19 BELOW.
- (3) EXISTING DEAERATOR SHALL REMAIN.

4 EXISTING CONDENSATE PIPING, MAKE-UP

- WATER, STEAM, ETC. SHALL REMAIN.
- $\langle 5 \rangle$ SEE SHEET ME101 FOR CONTINUATION. (6) REMOVE 6" - 300# BLIND FLANGE AND MAKE NEW CONNECTION FOR NEW 6" STEAM
- PIPING FROM NEW BOILER. PROVIDE NEW 6" -300# COMPANION FLANGE. (7) INSTALL STEAM FLOW TRANSMITTER WITH 3 VALVE MANIFOLD, PROVIDED BY BOILER MANUFACTURER. INSTALL PER
- (8) INSTALL NEW 6" -300# ANGLE NON-RETURN VALVE PROVIDED BY BOILER MANUFACTURER..

MANUFACTURERS INSTRUCTIONS.

- $\overline{\langle 9 \rangle}$ INSTALL NEW 6" -300# STEAM STOP VALVE PROVIDED BY BOILER MANUFACTURER.
- (10) CONTRACTOR SHALL INSTALL PRESSURE RELIEF VALVES (2) PROVIDED BY BOILER MANUFACTURER IF NOT ALREADY INSTALLED.
- (11) SEE DETAIL D5/ME501 FOR RELIEF VALVE
- (12) EXISTING 14" STEAM HEADER SHALL REMAIN.
- (13) NEW 6" STEAM SUPPLY PIPING FROM NEW BOILER.
- (14) EXISTING STEAM PIPING AND VALVE SHALL BE REUSED AS SHOWN.
- (15) EXISTING BOILER #3.
- $\langle 16 \rangle$ EXISTING BOILER #4.
- (17) 3/4" FREE BLOW DRAIN LINE. DRAIN VALVE SHALL BE PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY THIS CONTRACTOR FROM STEAM CONNECTION TO 3'-0" ABOVE FLOOR.
- (18) EXPANSION JOINT PROVIDED BY ECONOMIZER MANUFACTURER AND INSTALLED BY CONTRACTOR. COORDINATE WITH MANUFACTURER FOR EXACT LOCATION, SIZE, AND INSTALLATION INSTRUCTIONS.
- 19 NEW ECONOMIZER, ECONOMIZER INLET TRANSITION, AND ECONOMIZER OUTLET TRANSITION SHALL BE PROVIDED BY ECO THROUGH THE BOILER MANUFACTURER AND INSTALLED BY THIS CONTRACTOR. INSTALL PER MANUFACTURERS INSTRUCTIONS.
- 20 SEE LARGE SCALE DRAWING, SHEET ME201 FOR FUEL GAS RECIRCULATING DUCT AND CONNECTIONS.
- (21) EXISTING 6" STEAM PIPING FROM REMOVED BOILER #2; FROM MAIN STEAM HEADER TO VALVE SHALL REMAIN UNLESS PIPING AND VALVE ARE IN CONFLICT WITH THE INSTALLATION OF THE NEW ECONOMIZER AND STACK.
- 22 DROP TO EXISTING BLOWDOWN PIPING AND CONNECT TO EXISTING BLOWNDOWN LINE THAT WAS SERVING. REMOVE BOILER #2 SEE SHEET ME101 FOR CONTINUATION AND SHEET ME402 FOR LARGE SCALE OF BLOWDOWN SYSTEM.
- 23 NEW COEN BURNER. SEE LARGE SCALE PIPING PLAN ME201.
- (24) CONNECT 1-1/4" STEAM ATOMIZATION PIPE INTO 6" STEAM LINE FROM BOILER. ROUTE PIPING AS SHOWN.
- 25 DROP 1-1/4" ATOMIZATION STEAM LINE DOWN TO BURNER CONNECTION. SEE SHEET ME101 FOR CONTINUATION.
- 26> 1/2" CHEMICAL FEED PIPING. SEE SHEET ME101 FOR CONTINUATION.
- (27) DROP TO BLOW DOWN CONNECTION ON BOILER STEAM DRUM. SEE SHEET ME101 FOR CONTINUATION.
- (28) MINIMUM LENGTH OF STEAM PIPING FROM BOILER CONNECTION TO WEST ELL SHALL BE
- (29) EXISTING TOILET ROOM, STAIRS AND CATWALKS SHALL REMAIN.
- $\langle 30 \rangle$ 2" GAS VENT FROM BELOW OFF SET TO MISS STEAM PIPING AND ROUTE THRU ROOF. FIELD VERIFY ROUTING TO MISS STRUCTURAL, CONDUIT, PIPING ETC.
- (31) PROVIDE STEAM CONECTION FROM 6" STEAM SUPPLY TO BOILER AND ECONOMIZER SOOT BLOWERS. SIZING OF STEAM LINE TO SOOT BLOWERS SHALL BE PER SOOT BLOWER MANUFACTURER.
- (32) PROVIDE NEW HANDRAILS, TOE-PLATES ETC. FOR THIS AREA. SEE DETAIL C5/ME501.
- (33) CONNECT EXISTING EMERGENCY SHUT-OFF PUSH STATION TO NEW BOILER CONTROL

State of Utah Department of Administrative Services



Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



PROJECT NAME & ADDRESS

WEBER STATE UNIVERSITY HEATING PLANT -BOILER REPLACEMENT **DFCM No. 07049810**


Ogden, Utah

Wirth	DAIL		- 1	LVIOIOIV		
PROJECT	「 MANAGE	R:				


SLW/WP

04/11/08 WHW JOB NO.: 07037 SHEET TITLE

UPPER LEVEL BOILER ROOM EQUIPMENT PLAN



- (34) ECONOMIZER 3" 300# INLET AND OUTLET CONNECTIONS. PROVIDE 3" - 300# COMPANION FLANGE AT NEW CONNECTION.
- (35) EXISTING 4" BOILER FEEDWATER SUPPLY.
- (36) 2-1/2"- 300# BY-PASS GLOBE VALVE PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR.
- (37) NEW BLOWDOWN PIPING TO EXISTING BLOWDOWN PIPING IN EXISTING TRENCH. SEE DETAILS A2 AND C2/ME402. TANDEM VALVES SHALL BE PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR.
- (38) EXTEND 3/4" SOOT BLOWER DRAIN PIPING SIDE OF EXISTING BOILER AND TERMINATE WITH 3/4"- 800# GATE VALVE.
- (39) EXISTING 8x8 STEEL SUPPORT COLUMN.
- CONNECT TO EXISTING 2-1/2"- 300# VALVE FOR NEW BOILER FEEDWATER PIPING PROVIDE 2-1/2"- 300# COMPANION FLANGE.
- (41) GAS TRAIN PROVIDED BY BOILER CONTRACTOR INSTALLED BY CONTRACTOR.
- 42 PILOT BALL VALVE.
- (43) BOILER FEEDWATER CONTROL VALVE, GATE VALVE ETC. SHALL BE PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR.
- (44) 3/4"- 800# DRAIN VALVE AND SCH. 80 PIPING.
- (45) NEW FEEDWATER GATE VALVE AND CHECK VALVE- 300# 2-1/2". PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR.
- 46 ECONOMIZER INLET AND OUTLET TRANSITIONS PROVIDED BY ECONOMIZER MANUFACTURER AND INSTALLED BY CONTRACTOR.
- 47 LEAVE THIS PORTION OF CATWALK IN PLACE. SUPPORT FROM EXISTING POSTS AND PROVIDE NEW SUPPORT FROM EXISTING 8"x8" STEEL COLUMN.
- (48) EXISTING STAIRS AND LANDING SHALL REMAIN.





SHEET NOTES:

- (1) NEW 30,000 #1HR BOILER. PROVIDED BY OTHERS. CONTRACTOR SHALL UNLOAD BOILER AND INSTALL BOILER AS INDICATED.
- $\langle 2 \rangle$ NEW ECONOMIZER PROVIDED BY OTHERS. CONTRACTOR SHALL UNLOAD ECONOMIZER
- AND INSTALL AS INDICATED. (3) NEW BOILER FOUNDATION. SEE STRUCTURAL
- (4) EXISTING PIPING SHALL REMAIN.

DRAWINGS FOR DETAILS.

- (5) EXISTING 14" STEAM HEADER SHALL REMAIN.
- (6) NEW 1-1/2" SCH. 80 FUEL OIL SUPPLY.

(7) NEW 1-1/4" SCH. 80 FUEL OIL RETURN.

- (8) 1" SCH. 80 FUEL OIL SUPPLY TO CONNECTION ON BURNER. FIELD VERIFY ROUTING OF PIPING TO BURNER CONNECTION. PROVIDE 1" 600# BALL VALVE.
- 9 PROVIDE BACK PRESSURE VALVE. SEE SPECIFICATIONS.
- (10) NEW 3" NATURAL GAS. CONNECT TO GAS TRAIN PROVIDED WITH BOILER. CONTRACTOR SHALL INSTALL THE GAS TRAIN THAT WILL BE SHIPPED LOOSE WITH THE BOILER.
- (11) NEW 1/2" GAS PILOT LINE. CONNECT TO 3/8" GAS PILOT CONNECTION ON BURNER. FIELD VERIFY ROUTING OF PIPING TO BURNER CONNECTION.
- (12) NEW 1/2" CHEMICAL FEED PIPING. PROVIDE TRANSITION BETWEEN SCH. 80 PVC AND SCH. 80 CARBON STEEL AT THIS LOCATION.
- (13) INSTALL 1/2" 800# CHECK VALVE AND GATE VALVE PROVIDED BY BOILER MANUFACTURER. PROVIDE 1/2" 300# COMPANION FLANGE AT BOILER CONNECTION.
- (14) NEW 1" CONTINUOUS BLOWDOWN PIPING SCH. 80 CARBON STEEL. CONNECT TO BOILER CONNECTION WITH 1"- 300# COMPANION FLANGE.
- (15) EXISTING STEAM HEADER DRIP LEG SHALL
- (16) NEW NATURAL GAS METER. SEE SPECIFICATIONS.
- (17) NEW PRESSURE GAUGE.
- (18) NEW VENT PIPING FROM PILOT. FIELD VERIFY ROUTING OF VENT PIPING TO BURNER CONNECTION.
- (19) CONNECT NEW VENT PIPING CONNECTION ON GAS TRAIN. ROUTE GAS VENT UP AND THRU ROOF. FIELD VERIFY ROUTING OF VENT PIPING.
- 20 NEW 1-1/4" STEAM ATOMIZATION PIPING FROM NEW STEAM SUPPLY LINE. FIELD VERIFY ROUTING OF PIPING TO BURNER CONNECTION. USE SCH. 80 PIPING.
- (21) NEW 2-1/2" 300# GATE VALVES WITH CHAIN OPERATORS.
- (22) 3"x2-1/2" REDUCING ELL.
- 23> 10" DIA. FLUE GAS RECIRCULATING DUCT. PROVIDE BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR.
- (24) ROUTE STEEL STACK 17'-0" ABOVE ROOF WITH THREE GUY WIRES. SEE SPECIFICATION. PAINT STACK SAME COLOR AS EXISTING STACKS.
- (25) NEW 3/4" VENT CONNECTION AND VALVE. ROUTE DOWN THE SIDE OF THE BOILER AND TERMINATE WITH AN ADDITIONAL 3/4" 800# GATE VALVE. THE TOP 3/4" VALVE SHALL BE PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR. BOTTOM VALVE SHALL BE PROVIDED AND INSTALLED BY

CONTRACTOR. ALL PIPING SHALL BE SCH. 80.

- (26) NEW 3/4" DRAIN CONNECTION AND VALVE. ROUTE DOWN THE SIDE OF THE BOILER AND TERMINATE WITH AN ADDITIONAL 3/4" -800# GATE VALVE. THE 3/4" GATE VALVE SHALL BE PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR. BOTTOM VALVE SHALL BE PROVIDED AND INSTALLED BY CONTRACTOR. ALL PIPING SHALL BE SCH. 80.
- (27) TWO NEW PRESSURE RELIEF VALVES PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR. MOUNT ON BOILER FLANGE CONNECTIONS. PROVIDE ONE - 4" 150# COMPANION FLANGE FOR RELIEF VALVE #1 AND ONE 3" - 150# COMPANION FLANGE FOR RELIEF VALVE #2.
- 28 PROVIDE DRIP PAN ELL AND DRAIN PAN DOWN THE SIDE OF THE BOILER AND TERMINATE IN HEADER WITH 3/4"- 800# GATE VALVE. SEE DETAIL D5/ME501.
- 29 PROVIDE 3/4" DRAIN BETWEEN 6" NON-RETURN ANGLE VALVE AND 6" STOP VALVE. ROUTE 3/4" SCH. 80 DRAIN DOWN THE SIDE OF THE BOILER AND TERMINATE WITH 3/4" - 800# FREE BLOWDOWN VALVE. VALVE SHALL BE PROVIDED BY BOILER MANUFACTURER AND INSTALLED BY CONTRACTOR.
- (30) INSTALL NEW 6" STEAM PIPING FROM BOILER CONNECTION TO EXISTING 6" GATE VALVE **USED FOR EXISTING REMOVED BOILER #1** SEE SHEET ME101. PIPING SHALL BE ASME CODE PIPING FROM BOILER CONNECTION TO 6" STOP VALVE.
- (31) CONTRACTOR SHALL INSTALL 6" 300# ANGLE NON-RETURN VALVE AND 6" - 300# STOP VALVE PROVIDED BY BOILER MANUFACTURER. PROVIDE 6" - 300# COMPANION FLANGES AT BOILER CONNECTION AND AT VALVE CONNECTIONS.
- (32) CONDENSATE DRAIN FROM STEAM ATOMIZATION SYSTEM. ROUTE 3/4" SCH. 80 DRAIN LINE TO DRAINAGE SYSTEM.
- (33) PROVIDE UNIONS WHERE SHOWN AND AS APPLICABLE FOR ACCESS IN PIPING SYSTEM. UNIONS FOR STEAM, CONDENSATE, BOILER FEEDWATER, CHEMICAL FEET, BLOWDOWN, OIL SHALL BE S€H 80.

State of Utah Department of Administrative Services

Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



PROJECT NAME & ADDRESS

WEBER STATE UNIVERSITY **HEATING PLANT -BOILER** REPLACEMENT

DFCM No. 07049810

Ogden, Utah

MANAGE			

REVISION


SLW/WP

SHEET TITLE

MARK DATE


²/WINWARD M 04/11/08 WHW JOB NO.: 07037

BOILER ELEVATIONS



State of Utah

1			 		
PROJECT		R:			
	SLW		- Anna		




SHEET NOTES:

MANUFACTURER


A PIPE 3" SCH. 40 x SA-106-B-ASME CODE PIPE BY ECONOMIZER

CENTERLINES)-BY ECONOMIZER MANUFACTURER.

(B) FLANGE 3"-300# RFWN SCH. 40 BORE x SA-105 (NOTE: BOLT HOLES TO STRADDLE




B1 ECONOMIZER PLAN AND ELEVATIONS
SCALE: NONE



B3 EXPANSION JOINT SECTION

SCALE: NONE



LARGE SCALE ECONOMIZER ARRANGEMENT

State of Utah
Department of Administrative Services

Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



PROJECT NAME & ADDRESS

WEBER STATE
UNIVERSITY
HEATING PLANT BOILER
REPLACEMENT
DFCM No. 07049810

.

MARK DATE REVISION

PROJECT MANAGER:
SLW
DRAWN BY:

1. C.D.

DRAWN BY:

LGD
CHECKED BY:

SLW/WP
DATE:


04/11/08
WHW JOB NO.:


07037
SHEET TITLE

LARGE SCALE ECONOMIZER ARRANGEMENT


INTERMITTEN BLOWDOWN NOTES:

- 1 NEW 30,000 #/HR STEAM BOILER.
- 2 LOWER DRUM BLOWOFF TANDEM VALVES PROVIDED BE B&W INSTALLED BY THIS CONTRACTOR.
- $\langle 3 \rangle$ 1-1/2" BLOWDOWN PIPING TO FLANGE PROVIDED WITH BOILER.
- 4 NEW 1-1/2" -300# COMPANION FLANGES.
- (5) ASME CODE PIPING BETWEEN FLANGES AND
- FIRST VALVE. WELD ALL JOINTS. 6 CONNECT TO EXISTING 3" DIA. BLOWDOWN
- PIPING IN EXISTING TRENCH.
- $\langle 7 \rangle$ EXISTING 3" DIA. BLOWDOWN PIPING IN TRENCH..
- (8) EXISTING FLOOR TRENCH. SEE DETAIL D3/ME501.
- $\langle 9 \rangle$ 1'-2" FIELD VERIFY.
- (10) STEAM DRUM.
- (11) LOWER MUD DRUM.
- 12 NEW BOILER CONCRETE PAD. SEE STRUCTURAL DETAILS ON STRUCTURAL DRAWINGS.
- (13) FIELD VERIFY DEPTH OF TRENCH AT NEW
- CONNECTION LOCATION.
- (14) BOILER DRUM ACCESS MANWAY.
- (15) EXTERIOR EDGE OF BOILER.
- (16) FLOOR SUPPORTS MADE FROM 2" DIA. PIPE AND 4"x4"x1/4" FLOOR PLATE WITH TWO BOLTS. SEE DETAIL A1/ME501






BLOWDOWN PIPING PLAN









RENOVATED CONTINUOUS BLOWDOWN PIPING ELEVATION SCALE: 3/4" = 1'-0"

CONTINUOUS BLOWDOWN NOTES:

- $\langle 1
 angle$ EXISTING NIPPER, BLOWDOWN TANK, AND SUPPORTS SHALL REMAIN.
- $\langle 2 \rangle$ EXISTING CONCRETE PAD SHALL REMAIN.
- (3) 4X4 SUPPORT CHANNELS SHALL REMAIN.
- 4 EXISTING SUMP AND DRAIN SHALL REMAIN. $\langle 5 \rangle$ EXISTING EXTERIOR WALL.
- (6) CONTINUOUS BLOWDOWN FROM BOILER B-4 SHALL REMAIN.
- (7) CONTINUOUS BLOWDOWN FROM BOILER B-3 SHALL REMAIN.
- (8) CONTINUOUS BLOWDOWN FROM EXISTING BOILER B-2 SHALL BE REMOVED TO VALVE AND REPIPED AS SHOWN TO NEW BOILER B-2 ON SHEET ME101.
- $\langle 9 \rangle$ CONTINUOUS BLOWDOWN FROM EXISTING BOILER B-1 SHALL BE REMOVED TO HEADER TAKE-OFF AND CAPPED.
- (10) EXISTING SOFTENER TANKS SHALL REMAIN.
- (11) INTERMITTEN LOWER DRUM BLOWDOWN TANK SHALL REMAIN.
- (12) EXISTING 2" DIA. STEEL PIPE SUPPORT SHALL
- (13) EXISTING 1-1/2"x1-1/2" UNISTRUT SHALL
- REMAIN. (14) EXISTING BLOWDOWN HEADER SHALL
- REMAIN. (15) PROVIDE 1/2" NIPPLE AND CAP AT VALVE.
- (16) ALL EXISTING PIPING, VALVES, SUPPORTS ETC. SHALL REMAIN.
- (17) REMOVE AND REPLACE NEEDLE VALVE INTO EXISTING PIPING SERVING THE NEW BOILER #2. NEEDLE VALVE SHALL BE EQUAL TO.

State of Utah Department of Administrative Services

Division of Facilities

Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



WHW ENGINEERING INC. PROFESSIONAL MECHANICAL ENGINEERING 8619 Sandy Parkway Suite 101 SANDY, UTAH 84070 (801)466-4021, FAX 466-8536 EMAIL: excellence@whw-engineering.com

PROJECT NAME & ADDRESS


WEBER STATE UNIVERSITY **HEATING PLANT -BOILER REPLACEMENT**

DFCM No. 07049810

MARK	DATE	REV	ISION		
	TMANAGE SLW			*	
DRAWN			ESSIONAL	ENG	11


SLW/WP 04/11/08 WHW JOB NO.: 07037

> LARGE SCALE PLANS AND **ELEVATIONS BLOWDOWN SYSTEMS**














SHEET NOTES:


- REMOVE EXISTING FUEL OIL PUMPS AND REPLACE WITH NEW FUEL OIL PUMPS FOP-1,2 AND 3. SEE SCHEDULE SHEET ME601.
- REMOVE EXISTING PUMP BASES AND REPLACE WITH NEW PUMP CONCRETE PAD AS INDICATED. SEE DETAIL C3 SHEET ME501.
- (3) EXISTING FUEL OIL SUPPLY FROM UNDERGROUND STORAGE TANKS.
- 4 EXISTING FUEL OIL RETURN TO
- UNDERGROUND STORAGE TANKS.

 (5) CONNECT NEW PIPING TO EXISTING AT THIS
- LOCATION. FIELD VERIFY EXACT LOCATION.

 (6) EXISTING FUEL OIL SUPPLY SHALL REMAIN.
- $\overline{\langle 7 \rangle}$ EXISTING FUEL OIL RETURN SHALL REMAIN.
- $\overline{\langle 8 \rangle}$ EXISTING FUEL OIL SUPPLY HEADER SHALL
- 9 EXISTING FUEL OIL RETURN HEADER SHALL REMAIN.

REMAIN.

- (10) EXISTING FUEL OIL SUPPLY TO BOILER #3 SHALL REMAIN.
- (11) EXISTING FUEL OIL RETURN FROM BOILER #3 SHALL REMAIN.
- (12) EXISTING FUEL OIL SUPPLY TO BOILER #4 SHALL REMAIN.
- (13) EXISTING FUEL OIL RETURN FROM BOILER #4 SHALL REMAIN.
- REMOVE EXISTING FUEL OIL SUPPLY PIPING ETC. TO BOILER #1
- (15) REMOVE EXISTING FUEL OIL SUPPLY PIPING.
- (16) EXISTING 9'-0" ROLL-UP DOOR.
- (17) EXISTING 3'-0" MAN-DOOR.
- (18) WEST EXTERIOR WALL.
- (19) SEE FUEL OIL PUMP PIPING VALVES ETC. SHEET ME701.
- 20 PROVIDE PIPE CAP AT END OF HEADER.
- (21) EXISTING WATER SOFTENER PAD.
- NEW 6" HIGH CONCRETE PAD FOR NEW OIL PUMPS. SEE DETAIL C3/ME501. PROVIDE A 1-1/2" HIGH BY 2" WIDE CURB FOR CONTAINMENT.
- 23 EXISTING F.O.S. VALVES SHALL REMAIN.
- (24) EXISTING F.O.R. VALVES SHALL REMAIN.
- PROVIDE NEW 1-1/2" F.O.S. TO NEW BOILER #2. FOLLOW SAME ROUTING AS REMOVED PIPING. SUPPORT FROM WALL.
- PROVIDE NEW 1-1/4" F.O.R. FROM NEW BOILER #2 BACK TO EXISTING VALVE.
- PROVIDE NEW 1-1/2" F.O.S. FROM FOP-3 TO SUPPLY HEADER.
- PROVIDE CAP AT VALVE OUTLET FOR BOTH FUEL OIL SUPPLY AND RETURN SERVING REMOVED BOILER #1.
- 29 PROVIDE NEW DUAL BASKET STRAINER.
- PUMPS HAVE NOT BEEN SHOWN ON THE NEW PAD FOR CLARITY OF PIPING. CONTRACTOR SHALL MOUNT THE NEW PUMPS ON NEW PAD IN ACTUAL INSTALLATION.
- (31) EXISTING F.O.R. PIPING TO TANKS.
- 32 1-1/2" F.O.S. FROM NEW F.O.P-3
- 33 EXISTING PIPE SUPPORT SHALL REMAIN.







Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS




PROJECT NAME & ADDRESS

WEBER STATE
UNIVERSITY
HEATING PLANT BOILER
REPLACEMENT


DFCM No. 07049810

Ogden, Utal



LARGE SCALE
FUEL OIL PLAN VIEW AND

ELEVATIONS



							BOILE	ER SCH	IEDULE					
		DEGION	DEOLON	ODEDATINO	FURNACE		BOILER	FURNACE	ASME TOTAL	FORCED DRAFT	WEIGHT LBS.			MALCE AND
S	YMBOL	DESIGN CAPACITY	DESIGN PRESSURE	OPERATING PRESSURE	VOL. (CU. FT.)	TYPE	CONVECTION HEATING (SQ. FT.)	HEATING SURFACE (SQ. FT.)	BOILER HEATING SURFACE SQ. FT.	FAN MOTOR HP	EMPTY	HYDRO	OPERATIONAL	MAKE AND MODEL
(B 1						RE	MOV	ED —					
(B 2						RE	MOV	ED —					
V* (B 2	30,000 LBS./HR	250 PSIG	125 PSIG	633	D	2071	432	2503	25	47,500	62,600	58,400	B & W FM9-
(B 3						E>	(ISTIN	1G —					
	B 4						E>	(ISTIN	IG —					

1. BOILER IS FITTED WITH A COEN BURNER MODEL 760, DNX - 20.

2. PROVIDE 120V CONTROL CIRCUIT.

3. PROVIDE SERVICE FOR 40 HP FAN MOTOR.

NOTES:

BOILER IS BEING PURCHASED BY THE STATE OF UTAH. CONTRACTOR SHALL BE RESPONSIBLE FOR UNLOADING AND INSTALLATION. SEE SHEET ME703 FOR SCHEDULE

			FU	EL OIL	PUMP	SCHED	JLE				
SYMB OL TYPE MAKE / MODEL GPM P.S.I. SUCTION SIZE DISCHARGE SIZE MOTOR SE									SERVICE	SCHEDULE NOTES	
OL					OIZE	SIZE	V - Ø - Hz	HP	RPM		NOTES
FOP 1	ROTARY POSITIVE DISPLACEMENT	INGERSOLL DRESSER MODEL 4GASMIDO	15	150	1"	1"	208/3/60	3	1800	#2 FUEL OIL	
FOP 2	ROTARY POSITIVE DISPLACEMENT	INGERSOLL DRESSER MODEL 4GASMIDO	15	150	1"	1"	208/3/60	3	1800	#2 FUEL OIL	
FOP 3	ROTARY POSITIVE DISPLACEMENT	INGERSOLL DRESSER MODEL 4GASMIDO	15	150	1"	1"	208/3/60	3	1800	#2 FUEL OIL	

			В	DILER E	CONON	/IIZER	SCH	EDUL	E	
0)(1400)	FLUE GAS	HEATING SURFACE	DESIG	GN	RATED HEAT ABSORPTION		FOULING FACTOR		PRESSURE	MANUFACTURER
SYMBOL	SYMBOL FLOW RATE HEATING SURFA ACFM SQ. FT		TEMPERATURE	PRESSURE	BTUH	TUBE	SHELL	TUBE PSI.	SHELL PSI.	
(ECO)	-	1579	700 DEG. F	250 PSI	1,421,028	.00100	.0020	150	-	ECO-INC

1. ECONOMIZER IS BEING PURCHASED BY THE STATE OF UTAH.

CONTRACTOR SHALL BE RESPONSIBLE FOR UNLOADING AND INSTALLATION.

SEE SHEET ME703 FOR SCHEDULE.

1. SEE SPECIFICATIONS FOR OTHER APPROVED MANUFACTURERS.

2. PUMPS SHALL BE USED FOR PUMPING #2 FUEL OIL.

State of Utah
Department of Administrative Services

Division of Facilities Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



PROJECT NAME & ADDRESS

WEBER STATE
UNIVERSITY
HEATING PLANT BOILER
REPLACEMENT

DFCM No. 07049810

MARK DATE REVISION

PROJECT MANAGER:
SLW

DRAWN BY:
LGD


CHECKED BY:
SLW/WP


DATE:
04/11/08
WHW JOB NO.:
07037

SHEET TITLE

08 37


MECHANICAL SCHEDULES






State of Utah
Department of Administrative Services

Internet: http://www.dfcm.state.ut.us



BOILER FEEDWATER FLOW



NPL : NOMINAL PIPE THREAD

#	ITEM	PROVIDED BY	INSTALLED BY	SIZE	NOTES
31>	DRUM LEVEL TRANS. ISOLATION VALVES	B & W	CONTRACTOR	3/4"-800#-SW	S.L.
32	DRUM LEVEL TRANS. DRAIN VALVE	B & W	CONTRACTOR	1/2"-800#-SW	S.L.
33	NON-RETURN ANGLE VALVE	B & W	CONTRACTOR	6"-300#-FLG	S.L.
34	FREE BLOW DRAIN VALVE	B & W	CONTRACTOR	3/4"-800#-SW	S.L.
35>	ECONOMIZER VENT VALVE	B & W	CONTRACTOR	3/4"-800#-SW	S.L.
36	ECONOMIZER DRAIN VALVE	B & W	CONTRACTOR	3/4"-800#-SW	S.L.
37	STEAM STOP VALVE	B & W	CONTRACTOR	6"-300#-FLG	S.L.
38	LOWER DRUM DRAIN VALVE	B & W	CONTRACTOR	1"-800#-SW	S.L.
39>	STEAM SAMPLE VALVE	B & W	CONTRACTOR	1"-800#-SW	S.L.
40>	ATOMIZING STEAM STOP VALVE	B & W	CONTRACTOR	1-1/4"-800#-SW	S.L.
41>	ATOMIZING STEAM CHECK VALVE	B & W	CONTRACTOR	1-1/4"-800#-SW	S.L.
42	SOOTBLOWER ISOLATION VALVE	B & W	CONTRACTOR	2-1/2"-300#-FLG	S.L.
43	SOOTBLOWER DRAIN VALVE	B & W	CONTRACTOR	3/4"-800#-SW	S.L.
44	WINDBOX MTD. FD FAN W/ MOTOR & STARTER	COEN	B & W		
<u>45</u>	DRUM LEVEL TRANSMITTER	B & W	CONTRACTOR		S.L.
46	FGR DAMPER ACTUATOR	B & W	CONTRACTOR		S.L.
<u></u>	STEAM FLOW TRANSMITTER	B & W	CONTRACTOR		S.L.
48	FEED WATER FLOW CONTROLLER	B & W	CONTRACTOR		S.L.
49	FGR EXPANSION JOINT	B & W	CONTRACTOR		S.L.
50	FGR 10" DIA. DUCT	B & W	CONTRACTOR		S.L.
51	STEAM PRESSURE TRANSMITTER	COEN	CONTRACTOR		S.L.
52	ECONOMIZER INLET TRANSITION	ECO-INC.	CONTRACTOR		SDBV
53	ECONOMIZER OUTLET TRANSITION	ECO-INC.	CONTRACTOR		SDBV
54	BOILER OUTLET EXP. JOINT	ECO-INC.	CONTRACTOR		SDBV
	BOILER SOOTBLOWER	B & W	B & W		
	ECONOMIZER SOOTBLOWER	B & W	B & W		
 57>	ECONOMIZER SOOTBLOWER DRAIN VALVE	CONTRACTOR	CONTRACTOR	3/4"-800#-SW	
	EXISTING 6"-300# GATE VALVE	N/A	N/A		
	REMOVE EXISTING BLIND FLANGE AND REPLACE WITH NEW 6"-300# COMPANION FLANGE	CONTRACTOR	CONTRACTOR		
<u></u>	ECONOMIZER DRAIN AND VALVE	CONTRACTOR	CONTRACTOR	3/4"-800#-SW	
61)	FEEDWATER BYPASS AND VALVE	CONTRACTOR	CONTRACTOR	2-1/2"-250#-FLG'D	
		ABCOCK & WILCOX COMPANY		250" 1200	

LOOSE SHALL BE INSTALLED BY CONTRACTOR.

State of Utah (62) BOILER FEEDWATER INLET REMOTE Department of Administrative Services TEMPERATURE GAUGE 0-300° F BY

CONTRACTOR.

CONTRACTOR.

DEMOLITION PHASE.

TEMPERATURE GAUGE 0-300° F BY

GAUGE 0-250 PSIG BY CONTRACTOR.

GAUGE 0-250 PSIG BY CONTRACTOR.

AND SUPPORT FROM ECONOMIZER LEG

UNDER EACH GAUGE. BY CONTRACTOR.

(67) EXISTING MAIN STEAM HEADER PRESSURE INDICATOR SHALL REMAIN. TRANSMITTER AND RECORDER WAS RELOCATED DURING

INSTALLATION BY CONTRACTOR.

INSTALLATION BY CONTRACTOR.

AND INLET TO ECONOMIZER. BY

OF ECONOMIZER. BY CONTRACTOR.

SUPPORTS OR SUPPORTED FROM

ECONOMIZER STRUCTURE.

CONTRACTOR.

(69) RELOCATED BOILER FEEDWATER PRESSURE

SUPPORTS. PROVIDE IDENTIFICATION PLATE

TRANSMITTER AND RECORDER. CONNECT TO NEW BOILER STEAM DRUM CONNECTION. ALL

TRANSMITTER AND RECORDER. CONNECT TO NEW BOILER FEEDWATER CONNECTION. ALL

RECORDER FOR FLUE GAS BOILER OUTLET

RECORDER FOR STACK FLUE GAS OUTLET

Division of Facilities

Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



WHW ENGINEERING INC. PROFESSIONAL MECHANICAL ENGINEERING 8619 Sandy Parkway Suite 101 SANDY, UTAH 84070 (801)466-4021, FAX 466-8536

PROJECT NAME & ADDRESS

WEBER STATE UNIVERSITY **HEATING PLANT -BOILER** REPLACEMENT **DFCM No. 07049810**


MARK	DATE	REVISION	ON	
	Γ MANAGE			
,	SLW		COLLY.	
DDAWN			JONAL FA	

SLW/WP

PIPING & **INSTRUMENTATION DIAGRAM**



S.L. : SHIPPED LOOSE
SDBV : SHIPPED DIRECTLY BY VENDORS FLG : FLANGED CONNECTION SW : SOCKET WELD
FLG : FLANGED CONNECTION
SW : SOCKET WELD
NPL : NOMINAL PIPE THREAD



FEEDWATER SHEET NOTES:

FLANGES SHALL BE 300#.

RATING OF VALVE.

CONNECTION.

CONTRACTOR.

CONTRACTOR.

CONTRACTOR.

CONTRACTOR.

CONTRACTOR.

CONTRACTOR.

CONTRACTOR.

CONTRACTOR.

A1/ME501.

(1) BOILER AND ECONOMIZER CONNECTIONS:

ANY PIPING BETWEEN BOILER AND

ECONOMIZER FIRST VALVE SHALL BE ASME

2-1/2" GATE VALVE AND REPLACE WITH NEW

COMPANION FLANGE TO ECONOMIZER AND

COMPANION FLANGE. MATCH PRESSURE

2 ALL BFW JOINTS SHALL BE WELDED AND ALL

 $\langle 3 \rangle$ REMOVE BLIND FLANGE FROM EXISTING

4 PROVIDE NEW BFW PIPING FROM NEW

FROM ECONOMIZER TO BOILER

 $\langle 5 \rangle$ 2-1/2" - 300# FLG. BFW STOP VALVE.

(6) 2-1/2" -300# FLG. BFW CHECK VALVE.

(7) BFW CONTROL STATION, SHIPPED AS

IF NOT PROVIDED BY B&W.

PROVIDED BY B&W AND INSTALLED BY

PROVIDED BY B&W AND INSTALLED BY

ASSEMBLY FROM B&W AND INSTALLED BY

8 PROVIDE AND INSTALL 2-1/2"x1-1/2" REDUCER

9 2-1/2" -300# GATE VALVES PROVIDED WITH

ASSEMBLY FROM B&W. INSTALLED BY

(10) 1-1/2" -300# R.F. FLG. CONTROL VALVE WITH

ASSEMBLY FROM B&W. INSTALLED BY

(11) 2-1/2" -300# GLOBE VALVE. PROVIDED WITH

ASSEMBLY FROM B&W. INSTALLED BY

ECONOMIZER VENT. PROVIDED BY B&W AND

INSTALLED BY CONTRACTOR. PROVIDE AND

BOILER TO DRAIN HEADER C/W 3/4" -800# S.W.

ECONOMIZER DRAIN. PROVIDED BY B&W AND

BOILER TO DRAIN HEADER C/W 3/4" -800# S.W.

GLOBE VALVE. PROVIDED AND INSTALLED BY

INSTALLED BY CONTRACTOR. PROVIDE AND

EXTEND 3/4" DRAIN LINE DOWN SIDE OF

(17) 3"x2-1/2" REDUCING 90° ELL. PROVIDED AND

BLOW-DOWN VALVE, PROVIDED AND

(19) MOUNT CONTROL STATION 3'-0" FROM FLOOR

20 2-1/2" -300# FLG'D GATE VALVE WITH CHAIN WHEEL AND CHAIN. PROVIDED AND

21 2-1/2" -300# FLG'D BY-PASS GATE VALVE AND PIPING WITH CHAIN WHEEL AND CHAIN.

22 PROVIDE FLOOR SUPPORTS MADE FROM 2" DIA. PIPE WITH A 4"x4"x1/4" STEEL FLOOR PLATE BOLTED IN TWO PLACES INTO

(23) 3/4" DRAIN LINE AND 3/4" - 800# SW VALVE.

24 HANG FROM OVERHEAD STRUCTURE OR

SUPPORT FROM BOILER.

EXISTING CONCRETE FLOOR. SEE DETAIL

PROVIDED AND INSTALLED BY CONTRACTOR.

PROVIDED AND INSTALLED BY CONTRACTOR.

BALL VALVE. PROVIDED AND INSTALLED BY

EXTEND 3/4" VENT LINE DOWN SIDE OF

(12) EXISTING 4" BOILER FEED WATER.

(13) EDGE OF NEW ECONOMIZER.

(14) 3/4" -800# S.W. GATE VALVE FOR

⟨15⟩ 3/4" -800# S.W. GATE VALVE FOR

(16) 3" -300# COMPANION FLANGE.

INSTALLED BY CONTRACTOR.

(18) 2-1/2" -300# FLG'D STRAINER WITH


INSTALLED BY CONTRACTOR.

INSTALLED BY CONTRACTOR.


TO CENTERLINE OF PIPE.

NEW GAS TRAIN AND PIPING ISOMETRIC SCALE: NONE





BOILER FEEDWATER PIPING ISOMETRIC SCALE: NONE



- GAS TRAIN SHEET NOTES:
- 1 EXISTING 5" GAS PIPING.
- (2) CONNECT TO NEW 3" GAS VALVE PROVIDED BY DEMOLITION CONTRACTOR. FIELD VERIFY EXACT LOCATION OF CONNECTION.
- $\langle 3 \rangle$ GAS TRAIN SUPPLIED BY BOILER MANUFACTURER. GAS TRAIN WILL COME BROKEN DOWN. THIS CONTRACTOR SHALL ASSEMBLE GAS TRAIN AND INSTALL ALL PARTS, VALVES ETC. AS SHOWN.
- 4 PROVIDE FLOOR SUPPORTS MADE FROM 2 DIA. PIPE WITH A 4"x4"x1/4" STEEL FLOOR PLATE BOLTED IN TWO PLACES INTO EXISTING CONCRETE FLOOR. SEE DETAIL A1/ME501.
- $\langle 5 \rangle$ PRESSURE GAUGE, SNUBBER, AND VALVE, IF NOT PROVIDED WITH BOILER TRAIN SHALL BE
- PROVIDED AND INSTALLED BY CONTRACTOR. $\langle 6 \rangle$ 3" -150# FLG'D PLUG VALVE BY OTHERS.
- $\langle 7 \rangle$ 2-1/2" GAS PRESSURE REGULATOR. PROVIDED AND INSTALLED BY CONTRACTOR.
- $\langle 8 \rangle$ 3" -150# FLG'D STRAINER AND STRAINER BLOWDOWN BALL VALVE. PROVIDED AND INSTALLED BY CONTRACTOR.
- (9) 2" VENT THROUGH ROOF. PROVIDED AND **INSTALLED BY CONTRACTOR FROM POINT** SHOWN. FIELD VERIFY ROUTING OF VENT PIPING.
- (10) 3/8" GAS PILOT TAKE-OFF. PROVIDED AND INSTALLED BY CONTRACTOR.
- (11) PILOT GAS PRESSURE REGULATOR. PROVIDED AND INSTALLED BY CONTRACTOR.
- 12 PILOT GAS SHUT-OFF VALVE. PROVIDED AND INSTALLED BY CONTRACTOR.
- (13) SEE DETAIL A3/ME501 FOR PIPE ROOF PENETRATION. ALSO SEE D4/FS501.
- 14 PROVIDE 3" DIRT LEG.
- (15) PIPE HANGERS. PROVIDE 3'-0" FROM BOTH ENDS AND ONE IN CENTER. SEE DETAIL C1/ME501.
- (16) 3"x2-1/2" REDUCER BY CONTRACTOR.
- (17) 2"x1-1/4" REDUCER.
- (18) 3" BREAK-A-WAY FLANGES-PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- (19) GAS SAFETY SHUT-OFF VALVES AND SWITCHES ASSEMBLY-PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- ②O GAS VENT VALVE 1-1/4" NPT PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- ②1 GAS VENT MANUAL TEST VALVE 1-1/4" NPT -PART OF TRAIN. SEE NOTE 3 ABOVE.
- ②2〉 GAS FLOW CONTROL VALVE 3" -125# FF, FLG - PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- ②3 GAS MANUAL SHUT-OFF VALVE 3" NPT. PART
- OF GAS TRAIN. SEE NOTE 3 ABOVE. ②4〉 GAS SAFETY SHUT-OFF LEAK TEST VALVES 1/4" NPT -PART OF GAS TRAIN. SEE NOTE 3
- 25 INNER SPUD GAS CONTROL VALVE 3" BUTTERFLY - 125# -PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- ②6〉 OUTER SPUD GAS CONTROL VALVE -3" BUTTERFLY -125#- PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- GAS FLOW TRIM VALVE 3" -125# FF FLG. PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- 28 OUTER HEADER CONDENSATE DRAIN VALVE -1/2" NPT BALL- PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- 29 HIGH GAS PRESSURE SWITCH -1/4" NPT-PART OF GAS TRAIN. SEE NOTE 3 ABOVE.
- 30 INNER SPUD GAS PRESSURE GAUGE -2-1/2"Ø -0-30PSI- PART OF GAS TRAIN. SEE NOTE 3
- (31) OUTER SPUD GAS PRESSURE GAUGE -2-1/2"Ø -0-30PSI- PART OF GAS TRAIN. SEE NOTE 3
- 32 NEW GAS METER. SEE SPECIFICATIONS. METER SHALL BE SIZED TO PASS 36,864 SCFH OF NATURAL GAS AT 17 PSI.
- 33 GAS PIPING SHALL BE ROUTED OVER HEAD A MINIMUM OF 9'-6" FROM FLOOR TO CENTER LINE OF PIPE.
- (34) ALL GAS PIPING JOINTS SHALL BE WELDED
- EXCEPT WHERE INDICATED. 35 CONNECT VENT FROM PILOT VALVE TO NEW

PIPING VENT THRU-ROOF.

- (36) CONNECT VENT PIPING FROM MAIN PR VALVE AND PILOT. CONNECT TO 3" GAS MAIN AS
- REMOVE EXISTING 2" GAS CONNECTION TO 3" PLUG VALVE AND CAP EXISTING PIPING.

State of Utah Department of Administrative Services

Division of Facilities

Construction & Management 4110 State Office Building Salt Lake City, Utah 84114 Phone: (801) 538 - 3018 Fax: (801) 538 - 3267

Internet: http://www.dfcm.state.ut.us

CONSULTANTS



WHW ENGINEERING INC. ROFESSIONAL MECHANICAL ENGINEERING 8619 Sandy Parkway Suite 101 SANDY, UTAH 84070 (801)466-4021, FAX 466-8536

PROJECT NAME & ADDRESS

WEBER STATE UNIVERSITY **HEATING PLANT -BOILER** REPLACEMENT

DFCM No. 07049810


Ogden, Utah REVISION

MARK DATE

SLW/WP

07037

PIPING ISOMETRICS



I	POWER SYSTEMS SYMBOL LIST
SYMBOL	DESCRIPTION
	JUNCTION BOX - SIZE AND FUNCTION AS REQUIRED
	CONDUITS CONCEALED IN FLOOR OR BELOW GRADE
	CONDUITS CONCEALED IN CEILING AND WALLS
	ARROWS INDICATE HOME RUNS
	FUSED DISCONNECT SWITCH - SIZE AS REQUIRED
	COMBINATION STARTER/FUSED DISCONNECT SWITCH - SIZE AS REQUIRED
(5)	MOTOR LOCATION
	ELECTRICAL PANEL LOCATION
VFD	VARIABLE FREQUENCY DRIVE - BY DIV. 15000
$\times \times - \times$	MECHANICAL EQUIPMENT CALLOUT
\bigotimes	REFERENCE NOTE CALLOUT

		ELECTRICAL DATA					FEEDER SIZE		PROTECTION & STARTIN			RTING		
SYMB <i>O</i> L	. EQUIPMENT	HP	KM	FLA	MCA	VOLT/ PHASE	WIRE	GROUND	CONDUIT	DISCONNECT		STARTING FEATURE		COMMENTS
											N. FUSED	START ER	VFD	
B-2	BOILER	40		II5		208/3	3#1/0	1#6	I-I/2"	200/150				
B-2	BOILER CONTROL					120/1	2#12	I#I2	3/4"					2
FOP-I	ROTARY POSITIVE DISP.	3		10.6		208/3	3#I2	I#I2	3/4"	30/15		X		3
F0P-2	ROTARY POSITIVE DISP.	3		10.6		208/3	3#I2	I#I2	3/4"	30/15		X		3
FOP-3	ROTARY POSITIVE DISP.	3		10.6		208/3	3#12	I#I2	3/4"	30/15		×		3

3. PROVIDE STARTER IN EXISTING MOTOR CONTROL CENTER AND SITE DISCONNECT.

N.T.S.

BEAM CLAMP, HANGER CLAMP, OR APPROVED SUPPORT, AS

REQ'D BY WEIGHT


SUPPORTED


CONDUIT CLAMP -1/2"

1 1/4" TO 6"

SCALE:

TO I" UNISTRUT 2 PIECE CHANNEL PIPE STRAPS-







GYPSUM WALL BOARD


STRUCTURAL UNIT (BEAM, JOIST, SLAB, ETC.)

, ALL THREAD ROD-

SIZE AS REQUIRED







UNISTRUT CHANNEL- SIZE

- AS REQUIRED BY WEIGHT

TYPICAL CONDUIT RACK DETAIL

SUPPORTED

GENERAL NOTES:


CONTRACTOR.

- THE CONTRACTOR SHALL PATCH THE WALLS AND CEILINGS WHERE THE DEVICES ARE REMOVED TO MATCH THE EXISTING WALLS AND CEILINGS. COORDINATE WITH GENERAL
- (2) MINIMUM SIZE OF CONDUIT TO BE 3/4". ALUMINUM CONDUITS SHALL NOT BE USED.
- (3) USE RIGID STEEL SET SCREW TYPE FITTINGS ONLY. DIE CAST FITTINGS SHALL NOT BE USED. REFER TO THE MECHANICAL SHEETS FOR THE EXACT LOCATION OF THE MECHANICAL
- EQUIPMENT. (5) ALL NEW WORK MUST MEET THE CURRENT ADOPTED NATIONAL ELECTRICAL CODE.
- (6) NOT MORE THAN THREE (3) CIRCUITS, SHALL BE INSTALLED IN A CONDUIT. EACH CIRCUIT SHALL CONSIST OF I CONDUCTOR FOR EACH PHASE, I NEUTRAL, AND I GROUND, FOR A TOTAL
- OF FIVE CONDUCTORS. (7) THE MINIMUM SIZE OF THE CONDUCTORS ARE TO BE #12 AWG THAN COPPER, UNLESS INDICATED
- OTHERWISE ON THE DRAWINGS. (8) ALL J-BOXES SHALL HAVE MINIMUM DEPTH OF 2-1/8" UNLESS OTHERWISE SPECIFIED. SECURE ALL J-BOXES AS SHOWN IN THE DETAILS. FURNISH AND INSTALL PROPER MUD RINGS.
- ALL CONDUITS EXPOSED TO THE WEATHER AND IN THE BOILER ROOM SHALL BE GALVANIZED RIGID STEEL, UNLESS OTHERWISE NOTED.
- 10 ALL NEW EXPOSED CONDUIT MUST RUN AGAINST THE WALLS OR CEILINGS. DO NOT PENDANT MOUNT ANY CONDUIT FROM THE CEILINGS.
- AT THE END OF THE JOB, PROVIDE BLANK COVER PLATES TO MATCH THE OTHER COVER PLATES FOR ALL J-BOXES WHERE DEVICES HAVE NOT YET BEEN INSTALLED.
- © SEAL AROUND ALL CONDUIT PENETRATIONS THROUGH FIRE RATED WALLS AND CEILINGS WITH FIRE RATED MATERIAL. 3M IS AN APPROVED MANUFACTURER.
- (13) ALL DISCONNECTS SHALL BE HEAVY DUTY TYPE. (14) ALL MATERIALS USED IN THIS INSTALLATION SHALL BE U.L. APPROVED AND NEW.
- (15) ALL ELECTRICAL WIRING MUST BE IN CONDUIT (ROMEX AND MC CABLE NOT PERMITTED).
- 16 FLEXIBLE CONDUITS CAN ONLY BE USED FOR SHORT RUNS (6' MAXIMUM).
- (17) NO CONDUITS SHALL RUN IN DUCT WORK.
- (R) PRIOR TO SUBMITTING A BID THE ELECTRICAL CONTRACTOR SHALL INSPECT THE SITE AND INCLUDE IN HIS BID PACKAGE ALL CHARGES DUE TO EXISTING CONDITIONS. SHOP DRAWINGS ARE REQUIRED. ALL LABOR, MATERIAL AND WORKMANSHIP SHALL BE GUARANTEED FOR A PERIOD OF I YEAR FROM THE DATE OF ACCEPTANCE BY THE TENANT. REPLACE OR REPAIR ALL DEFECTS DURING THE GUARANTEED PERIOD.
- THE ELECTRICAL CONTRACTOR SHALL TERMINATE THE ELECTRICAL CONNECTIONS TO ALL THE EQUIPMENT BY PROVIDING THE NECESSARY MALE/FEMALE CONNECTOR, RECEPTACLE,
- ALL DUPLEX OUTLETS AND SWITCHES SHALL BE 20 AMP., 120 VOLT SPEC GRADE. HUBBELL
- AND PASS & SEYMOUR AND LEVITON ARE APPROVED MANUFACTURERS. THE ELECTRICAL CONTRACTOR SHALL NOTIFY AND COORDINATE WITH THE MECHANICAL CONTRACTOR SO THAT NO PIPING, DUCTS, OR OTHER EQUIPMENT SHALL BE INSTALLED IN ENTRY OR PASS THROUGH ELECTRICAL ROOM OR SPACES ABOVE OR BELOW ELECTRICAL
- ② ELECTRICAL CONTRACTOR SHALL VERIFY ALL ELECTRICAL LOADS (VOLTAGE, PHASE, CONNECTION REQUIREMENT, ETC.) OF EQUIPMENT FURNISHED UNDER OTHER DIVISIONS WITH APPROVED SHOP DRAWINGS PRIOR TO BEGINNING ROUGH-IN.
- THE CONTRACTOR SHALL INFORM THE ARCHITECT/ENGINEER IN WRITING OF ANY DISCREPANCIES FOUND BETWEEN THE INTENDED FUNCTION OF EQUIPMENT AND EQUIPMENT SPECIFIED IN THE CONTRACT DOCUMENTS A MINIMUM OF FIVE (5) WORKING DAYS PRIOR TO ISSUANCE OF THE FINAL BID. FAILURE TO REPORT ANY DISCREPANCY (CATALOG NUMBERS, DISCONTINUED ITEMS, ETC.) DOES NOT RELIEVE THE CONTRACTOR FROM PROVIDING EQUIPMENT WHICH SHALL CONFORM TO AND FULFILL THE INTENT OF THE CONTRACT DOCUMENTS. NOR SHALL IT BE USED AS A CONDITION TO OBTAIN ADDITIONAL FUNDS FROM THE OWNER AFTER THE CONTRACT IS AWARDED. THE CONTRACTOR SHALL REQUEST ALL CLARIFICATIONS OF CONTRACT DOCUMENT REQUIREMENTS IN WRITING TO THE ARCHITECT/ENGINEER A MINIMUM OF FIVE (5) WORKING DAYS PRIOR TO ISSUANCE OF THE
- PROVIDE TYPED LABEL FOR ALL DUPLEX OUTLETS AND LIGHT SWITCHES TO INDICATE WHICH CIRCUIT THEY ARE TIED TO.
- (5) CONTRACT DOCUMENTS SHALL TAKE PRECEDENCE OVER SHOP DRAWINGS UNLESS

KEPT SHOWING THAT ALL CAPS ARE REMOVED AND ACCOUNTED FOR.

- (6) TO MINIMIZE NUMBER OF FALSE FIRE ALARM DURING CONSTRUCTION, THE CONTRACTOR SHALL CAP SMOKE DETECTORS IN AREAS ADJACENT TO WORK SITE WHILE DUST-GENERATING WORK IS PERFORMED. THESE CAPS SHALL BE REMOVED AT END OF WORKDAY. COORDINATE THE EXTENT OF DEVICE CAPPING REQUIRED WITH CAMPUS FIRE MARSHALL. A LOG SHALL BE
- (7) IF, FOR ANY REASON FIRE ALARM SYSTEM CANNOT BE RETURNED TO SERVICE AT THE END OF WORK DAY THE CAMPUS FIRE MARSHALL MUST BE NOTIFIED. CONTRACTOR SHALL PROVIDE FIRE WATCH AT NO ADDITIONAL COST TO THE OWNER.
- USE NO. 10 THHN CONDUCTORS FOR CONDUCTOR LENGTH OVER 100 FEET, NO. 8 THHN OVER 200 FEET, NO. 6 THHN OVER 300 FEET AND NO. 4 THHN OVER 400 FEET LENGTH.

State of Utah Department of Administrative Services



Internet: http://www.dfcm.state.ut.us

CONSULTANTS






Electrical Consulting Engineers 939 So. West Temple Salt Lake City, Utah 84101 Telephone (801) 521-8007 Telefax (801) 521-8057

PROJECT NAME & ADDRESS

WEBER STATE UNIVERSITY HEATING PLANT - BOILER REPLACEMENT

DFCM No. 07049810

Ogden, Utah



CHECKED BY: A.M. 04/11/08 ECE JOB NO.:

GENERAL NOTES,

SCHEDULES AND DETAILS

EE001

